

## WELL PLUGGING RECORD

STATE OF KANSAS  
STATE CORPORATION COMMISSION

**Give All Information Completely**  
**Make Required Affidavit**  
**Mail or Deliver Report to:**  
**Conservation Division**  
**State Corporation Commission**  
**300 Bitting Building**  
**Wichita, Kansas**

**OR**

**Strike out upper line when reporting plugging off formations.**

## FORMATION PLUGGING RECORD

NORTH

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

**Locate well correctly on above  
Section Plat**

State Corporation Commission  
300 Bittling Building  
Wichita, Kansas

NORTH

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Rooks County. Sec. 22 Twp. 10 Rge. 4 (E) 16 (W)  
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 330'S 330'E of NW Corner  
 Lease Owner Cities Service Oil Company  
 Lease Name Camp Well No. 1  
 Office Address Bartlesville, Oklahoma  
 Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
 Date well completed 4-7 19 48  
 Application for plugging filed 7-15 19 48  
 Application for plugging approved 7-15 19 48  
 Plugging commenced 7-17 19 48  
 Plugging completed 7-23 19 48  
 Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production.....19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well..... M. A. Rives      Box 105      Hays, Kansas  
Producing formation..... KC Lime..... Depth to top 3084..... Bottom..... Total Depth of Well 3343..... Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

### CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to .....feet for each plug set.

Filled with sand from 3343 to 3061'. Dumped 5 sacks cement filled with mud to 225 feet, set bridge, dumped 15 sacks cement mud to 25 feet, dumped 10 sacks cement to surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to **Mr. R. C. Cooper**  
Address **Cities Service Oil Co. Great Bend, Kansas**

STATE OF Kansas, COUNTY OF Barton, SS.


Mr. James Foster (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 553 Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of

My commission expires \_\_\_\_\_



15-163-63482-00-00

## WELL RECORD

Company Citizen Service Oil Co. Well No. 1 Farm Comp  
 Location 300' South and 300' East of N. Corner. Sec. 12 T. 10 R. 16  
 Elevation 1933 (1935 C.). County Rock State Kansas  
 Drlg. Comm. 2-6-48 Contractor R. G. Sine Drilling Co.  
 Drlg. Comp. 2-22-48 Acid 9000 gallons (see below).  
 T. D. 3343' Initial Prod. 12 oil, 22 water, 8 hours (2-6-48).

CASING RECORD:

8-5/8" @ 230' with 150 sacks cement 100% C.C.

4-1/2" @ 3343' with 150 sacks cement.

FOUNTAIN RECORD:

|                                                           |           |
|-----------------------------------------------------------|-----------|
| sand                                                      | 0-40      |
| shale and shells                                          | 230       |
| shale and lime                                            | 315       |
| shale, shells and sand                                    | 1030      |
| shale and shells                                          | 1095      |
| anhydrite                                                 | 1150      |
| shale and shells                                          | 1260      |
| shale and lime                                            | 1320      |
| lime and shale                                            | 1380      |
| lime                                                      | 2400      |
| lime and shale                                            | 3465      |
| Twisted off drill pipe; could not recover fish.           |           |
| Cemented 1663' to 1416' with 200 sacks cem. and 300% C.C. |           |
| shale and lime                                            | 1416-1735 |
| lime and shale                                            | 2423      |
| shale and lime                                            | 2545      |
| lime and shale                                            | 3010      |
| lime                                                      | 3120      |
| lime and shale                                            | 3180      |
| lime                                                      | 3343 T.D. |

|                    |       |
|--------------------|-------|
| Top Landing        | 3004' |
| Perforation        | 259'  |
| Total depth        | 3343' |
| Perf. Pen. Landing | 261'  |

Drilled cement to 3'43'.

Perforate 26 shots 3133-95 small show oil.  
 Perforate 36 shots 3133-50 small show oil.  
 Perforate 30 shots 3119-27 small show oil.  
 Perforate 30 shots 3083-93 small show oil.  
 Perforate 30 shots 3061-69 small show oil.

3-16-48 acidized 1000 gallons 3061-69

" " 1000 gallons 3083-93

" " 1000 gallons 3119-27

" " 1000 gallons 3133-50

" " 1000 gallons 3133-95

3-20-48 pumped 12 oil, 29 water, 24 hours.

3-23-48 Pumped 15 oil, 17 water, 24 hours.

Perforate 16 shots 3331-33

Perforate 24 shots 3230-3304

Perforate 24 shots 3274-60

Perforate 24 shots 3228-34

3-28-48 acidized 1000 gallons 3331-33

" " 1000 gallons 3230-3304

" " 1000 gallons 3274-60

" " 1000 gallons 3228-34

SLOPE TESTS ( acid bottle)

300' OK

1000' OK

1500' OK

2000' OK

3000 (after fishing job):

1500' 1°

1700' 1°

1850' 1°

1950' 1°

2077' 0°

2300' 0°

2650' 0°

7-7/8" rotary hole.

