

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: White Pine Petroleum Corporation  
Address: 110 S Main, Suite 500, Wichita, KS 67202  
Phone: (316) 262-5429 Operator License #: 5044  
Type of Well: OG PercP2/3 PerKCC Docket #: 12/28/06  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 12/08/06 (Date)  
by: Steve Durrant (KCC District Agent's Name)

API Number: 15-185-22333-00-01 9-11-08  
Lease Name: Cornwell  
Well Number: 1-31 NE SE SW NE 6 PS  
Spot Location (QQQQ): NO SW SE NE  
3148 Feet from  North /  South Section Line Per 6 PS  
1237 Feet from  East /  West Section Line  
Sec. 31 Twp. 23 S. R. 13  East  West  
County: Stafford  
Date Well Completed: 4-24-86  
Plugging Commenced: 12-5-06  
Plugging Completed: 12-8-06

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
MISSISSIPPI Depth to Top: 3907 Bottom: 3920 T.D. 4125  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 4072  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. Per 6 PS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	305	
				5 1/2	4124	1810'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.  
Sand at 3760', resanded well, sand at 3620', bailed 5 sacks cement, stretched pipe, cut 2422', not loose, cut 2230', not loose, cut 2010', not loose, pulled collar off casing, welded slip collar back on, cut 1810', came loose, pulled casing to 725', pumped 15 gel, 50 sacks, pulled to 325', pumped 50 sacks, pulled to 40', pumped 10 sacks, tore down floor and rig.

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
DEC 20 2006  
CONSERVATION DIVISION  
WICHITA, KS

Name of Plugging Contractor: Quality Well Service License #: 31925  
Address: 401 W Main, Lyons, KS 67554  
Name of Party Responsible for Plugging Fees: White Pine Petroleum Corporation  
State of KANSAS County, SEDGWICK, ss.

WILBUR C BRADLEY (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

**RICHARD A. PAPE, JR.**  
Notary Public - State of Kansas  
My Appt. Expires 8/14/08

(Signature) Wilbur C Bradley  
(Address) 110 S. MAIN, SUITE 500 WICHITA, KS 67202

SUBSCRIBED and SWORN TO before me this 19TH day of DECEMBER, 2006  
Richard A. Pape, Jr. Notary Public My Commission Expires: 8/14/2008