

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Brungardt Oil & Leasing, Inc.
Address: PO Box 871, Russell, KS 67665
Phone: (785) 483-4975 Operator License #: 3956
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10-17-08 (Date)
by: Pat Staab (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, Is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-141-20,392-00-00
Lease Name: Angel "B"
Well Number: 1
Spot Location (QQQQ): _____ - NE - NW - SW
2,240 Feet from North / South Section Line
670 Feet from East / West Section Line
Sec. 31 Twp. 10 S. R. 14 East West
County: Osborne
Date Well Completed: 10-16-08
Plugging Commenced: 10-17-08
Plugging Completed: 10-17-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	234'	Cmtd. w/160 sax

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run drill pipe to 3,445', pump 25 sax cement thru drill pipe; run drill pipe to 985', pump 25 sax cement thru drill pipe; run drill pipe to 518', pump 100 sax cement thru drill pipe; run drill pipe to 284', pump 40 sax cement thru drill pipe; push wiper plug to 40', dump 10 sax cement on plug to cellar. Circulate 30 sax cement down rat hole and 15 sax cement down mouse hole. Oil Producers Inc.

Name of Plugging Contractor: Shields Drilling Co. License #: 5184 RECEIVED
Address: PO Box 709, Russell, KS 67665 KCC PKT per CP 2/3 KANSAS CORPORATION COMMISSION


Name of Party Responsible for Plugging Fees: Brungardt Oil & Leasing, Inc. OCT 27 2008

State of KANSAS County, RUSSELL, ss. CONSERVATION DIVISION
Burton Beery, Drilling Supt. Contractor WICHITA, KS

(Employee of Operator or Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Burton Beery
(Address) P.O. Box 709 Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 24th day of October, 2008
Ruth Phillips Notary Public My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202




Shields

Russell, Kansas

WELL LOG

Operator: Brungardt Oil & Leasing, Inc.
 Well: Angel "B" #1
 Commenced: 10-9-08
 Completed: 10-17-08
 Contractor: Shields Drilling Co.

Well Description: 2,240' FSL, 670' FWL
 SW/4 Sec. 31-10S-14W
 Osborne Co., KS



CASING RECORD

Size	Run	Pulled
8 5/8"	234'	Cmtd. w/160 sax

Elevation: 1,823 KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Sand & shale	350'
Sand	555'
Sand & redbed	971'
Anhydrite	1,004'
Redbed & shale	1,350'
Shale	1,580'
Shale & lime	2,655'
Lime	3,465'
Arbuckle	3,530' RTD

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 27 2008

CONSERVATION DIVISION
WICHITA, KS

Notes