

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Jody Oil & Gas Corporation

Address: PO Box 422, Attica, KS 67009

Phone: (620) 254-7251 Operator License #: 3288

Type of Well: Oil - Gas KCCPKT per CPA/3 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Miss Depth to Top: 4491 Bottom: 4495 T.D. 4560

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	245	
Miss	Oil/Gas	4491	4495	4 1/2	4567	1880

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 4430', bailed 4 sacks cement, had 15" stretch, ripped casing at 3020', worked pipe, ripped casing at 2040', worked pipe, ripped casing at 1880', pipe came free, pulled casing up to 600', pumped 10 gel, 50 sacks at 600', pulled to 280', pumped 50 sacks, pulled to 40', pumped 20 sacks, emptied pit.

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925 MAR 20 2008


Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Jody Oil & Gas Corporation CONSERVATION DIVISION WICHITA, KS

State of Kansas County, Harper, ss.

Randy Newberry (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Randy Newberry
(Address) PO Box 195, Attica, KS 67009



SUBSCRIBED and SWORN TO before me this 19th day of March, 2008
Jane Swingle My Commission Expires: 1-6-2011
Notary Public, Jane Swingle

