

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior, Inc.
Address: P. O. Box 399, Garden City, KS 67846
Phone: (620) 275-2963 Operator License #: 4058
Type of Well: OIL Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5-18-06 (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
ARB Depth to Top: 3329' Bottom: 3338' T.D. 3338
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-21,175-00-00
Lease Name: Wondra
Well Number: 1
Spot Location (QQQQ): _____ - SW - SE - SE
330 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 4 Twp. 17 S. R. 12 East West
County: BARTON
Date Well Completed: 7-5-77
Plugging Commenced: 5-18-06
Plugging Completed: 5-18-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	SURFACE	215'	8-5/8"	215'	None
	Production	SURFACE	3332'	4-1/2"	3332'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated 1450', 775'. 380' Ran tbg to 2000' pump 75 sks Cement & 300# Hulls pulled tbg to 1000'. circulated 160 sks cement & 200#'s Hulls pull tbg, pumped 60 sks cement down csg, SI press 300 #'s, pump 25 sks cement into back side. SI 200 #'s cut off csg. Fill cellar

Name of Plugging Contractor: Well Express Service & Supply Inc License #: 6426
Allied Cementing Co License #: 6426
Address: P. O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: American Warrior, Inc.
State of Kansas County, Finney, ss.

Nancy E. Davis, Compliance Coordinator
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
(Address) American Warrior, Inc. P.O. Box 399, Garden City, KS 67846

SUBSCRIBER and SWORN TO before me this 22nd day of October, 20 08
[Signature] My Commission Expires: 09-12-09
Notary Public

[Handwritten initials]