

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Rosewood Resources, Inc.
Address: 2711 N. Haskell Ave., Suite 2800, LB 22
Phone: (970) 324-1686 Operator License #: 33019
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Herb Dennis (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Niobrara Depth to Top: N/A Bottom: N/A T.D. 373'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-181-20459-00-00
Lease Name: Beachner Bros
Well Number: 14-24H
Spot Location (QQQQ): SE SW - SE - SW - SW *KCC PKT CAPS.*
125 Feet from North / South Section Line
850 Feet from East West Section Line
Sec. 24 Twp. 7 S. R. 39 East West
County: Sherman
Date Well Completed: N/A
Plugging Commenced: 10/8/2008
Plugging Completed: 10/8/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Ogallala	Water	Surface	373'	7'		
Niobrara	Gas					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug 100' -- Surface 17.8 sks #1 Neat cmt

KCC PKT Pm CP2/B

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 21 2008
CONSERVATION DIVISION
WICHITA, KS

Name of Plugging Contractor: Advanced Drilling Technologies LLC License #: 33532
Address: PO Box 203, Yuma, Colorado, 80759

Name of Party Responsible for Plugging Fees: Rosewood Resources, Inc.
State of Kansas County, Cheyenne, ss.

Tom W. Roelfs (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Tom W Roelfs
(Address) PO Box 926, St. Francis, KS 67756

SUBSCRIBED and SWORN TO before me this 15 day of October 2008
Carla S Lampe My Commission Expires: 12/1/2010
Notary Public - State of Kansas
CARLA S. LAMPE
Notary Public - State of Kansas
My Appl. Expires

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT

LEASE DESCRIPTION: Beachner Bros 14-24H

Rosewood Resources

LOCATION: 125' FSL & 850' FWL, SWSW/4 Section 24-T7S-R39W 320'

ELEV: 3585' GR

COUNTY: Sherman STATE: Kansas API #: 15-181-20459-01 Spvr: Wayne

FIELD: Goodland

11/07/06: MIRU SCHAAL DRILLING CO. PREVIOUS 24 HRS - SPUD SURFACE @ 8:30 AM ON 11/06/06. 9 1/2" HOLE DRILLED 0' TO 373'. TD @ 11:15 AM. CIRC. TOOH. RAN 9 JTS OF 7", 17# CSG MEAS 367'. SET @ 380'. CMT W/ 100 SKS OF TYPE 1 NEAT CMT. CIRC 2 BBL TO PIT. PLUG DOWN @ 1:30 PM. RDMO.
SHALE @ 290'

10/18/07: MIRU ROSEWOOD SLICKLINE, SWABBED WELL TO 100'. RDMO

10/8/08: MIRU ROSEWOOD SLICKLINE, SWABBED WELL TO 100' OF WATER, RDMO. MIRU LONGHORN CMTRS, PUMPED 0 - 100' CMT PLUG W/ 17.8 SKS #1 NEAT CMT (4.1 BBL). RDMO LONGHORN

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 21 2008

CONSERVATION DIVISION
WICHITA, KS