

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Rosewood Resources, Inc.  
Address: 2711 N. Haskell Ave., Suite 2800, LB 22  
Phone: (970) 324-1686 Operator License #: 33019  
Type of Well: Gas Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Herb Dennis (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Niobrara Depth to Top: N/A Bottom: N/A T.D. 372'  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-181-20464-00-00  
Lease Name: Beachner Bros  
Well Number: 34-24H  
Spot Location (QQQQ): SE - SW - SW - SE  
125 Feet from  North /  South Section Line  
2030 Feet from  East /  West Section Line  
Sec. 24 Twp. 7 S. R. 39  East  West  
County: Sherman  
Date Well Completed: N/A  
Plugging Commenced: 10/8/2008  
Plugging Completed: 10/8/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Ogallala	Water	Surface	372'	7"		
Niobrara	Gas					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug 100' -- Surface 17.8 sks #1 Neat cmt

KCC PKT Per CP 2/3  
Advanced Drilling Technologies LLC  
Name of Plugging Contractor: Lonehorn Cementing Company License #: 33532  
Address: PO Box 203, Yuma, Colorado, 80759

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Rosewood Resources, Inc.  
State of Kansas County, Cheyenne, ss.


OCT 21 2008

Tom W. Roelofs (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Tom W Roelofs  
(Address) PO Box 926, St. Francis, KS 67756

SUBSCRIBED and SWORN TO before me this 16 day of October 2008  
Carla S. Lampe My Commission Expires: 12/1/2010  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*PKA*



LEASE DESCRIPTION: Beachner Bros 34-24H

LOCATION: 125' FSL & 2030' FEL, SWSE/4 Section 24-T7S-R39W 320'

COUNTY: Sherman STATE: Kansas API #: 15-181-20464-01 Spvr: Wayne

Rosewood Resources

ELEV: 3582' GR

FIELD: Goodland

**11/08/06:** MIRU SCHAAL DRILLING CO. PREVIOUS 24 HRS - SPUD SURFACE @ 7:45 AM ON 11/07/06. 9 1/2" HOLE DRILLED 0' TO 372'. TD @ 10:15 AM. CIRC. TOOH. RAN 9 JTS OF 7", 17# CSG MEAS 367'. SET @ 380'. CMT W/ 100 SKS OF TYPE 1 NEAT CMT. CIRC 3 BBL TO PIT. PLUG DOWN @ 11:45 AM. RDMO.  
SHALE @ 295'

**10/18/07:** MIRU ROSEWOOD SLICKLINE, SWABBED WELL TO 100'. RDMO

**10/8/08:** MIRU ROSEWOOD SLICKLINE, SWABBED WELL TO 100' OF WATER, RDMO. MIRU LONGHORN CEMENTERS, PUMPED 0 - 100' CEMENT PLUG W/ 17.8 SKS #1 NEAT CMT (4.2 BBL). RDMO LONGHORN

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 21 2008

CONSERVATION DIVISION  
WICHITA, KS