

15-179-20150-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sheridan County, Sec. 30 Twp. 10 Rge. 26 (E) W (W)

Location as "NE/CNW/SW" or footage from lines. C NE SW

Lease Owner Leo J. Dreiling Oil Company

Lease Name Tilton Well No. #1

Office Address R. R. #2; Victoria, Kansas 67671

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19 70

Application for plugging filed August 19 70

Application for plugging approved August 19 70

Plugging commenced August 24 19 70

Plugging completed August 27 19 70

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 8-13 19 70

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	177	None
				4 1/2	4039	1150

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1970
CONSERVATION DIVISION
Wichita, Kansas
09-04-1970

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

August 24, 1970 Plugged off bottom. Dumped sand to 3775'. Mixed and dumped 4 sx of cement to 3725'.

August 27, 1970 Plugged off top. Sun Oil Well Cementing Co. mixed and pumped down 8 5/8" surface casing:
5 sx hulls
10 sx gel
100 sx cement
17 sx gel
Released plug, mixed and pumped 25 sx of cement,
3 sx gel and 10 sx of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. BOX 1082 ; GREAT BEND, KANSAS 67530

STATE OF KANSAS, COUNTY OF ELLIS, ss.
LEO F. DREILING (PARTNER or (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling (Address)

Subscribed and sworn to before me this 2nd day of SEPTEMBER, 1970

My commission expires SEPTEMBER 19, 1970

Joseph A. Hess Notary Public.



L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

WELL LOG

Company: Leo J. Dreiling Oil Company
 Route 2
 Victoria, Kansas 67671

15-179-20150-00-00
 Sec. 30 Twp. 10 Rng. 26

Farm: Tilton No. 1 Location: G NE SW

Total Depth: 4370' County: Shoridan

Comm. 10-16-68 Comp. 10-25-68 Elevation: 2544' K. B.
 2541' D. F.
 2539' G. R.

Contractor: L. J. Dreiling & Sons, Inc.
 Victoria, Kansas 67671

Casing Record
 177' - 8 5/8"
 4039' - 4 1/2"

Cement Record
 160 sacks cement
 200 sacks 50/50 Pozmix, 2%
 gel, 10% salt, 1% C.C. with 9'
 Friction Reducer

Production:

Figures Indicate Bottom of Formations

0'	20'	Surface Soil & Clay
20'	27'	Sand
27'	38'	Orange Clay
38'	40'	Shale
40'	90'	Yellow Clay
90'	177'	Blue Shale
177'	1080'	Shale
1080'	1245'	Shale & Sand
1245'	1545'	Shale & Gyp
1545'	1620'	Shale
1620'	1670'	Shale & Gyp
1670'	1780'	Shale & Redbed
1780'	1940'	Shale & Sand
1940'	2150'	Redbed & Shale
2150'	2185'	Anhy.
2185'	2207'	Anhy.
2207'	2515'	Shale
2515'	3590'	Line & Shale
3590'	4075'	Line
4075'	4370'	Line & Shale
4370'	T.D.	

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 24 1970
 CONSERVATION DIVISION
 Wichita, Kansas

08-24-1970


STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc, upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Tilton #1.

Leo F. Dreiling
 LEO F. DREILING

Subscribed and sworn to before me this 28th day of October 1968.

Joseph A. Hess
 JOSEPH A. HESS NOTARY PUBLIC



My commission expires: September 19, 1970