

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 19 1962  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Graham

Location: NE NE SW Sec. 7 Twp. 10 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 25

Name of Field: \_\_\_\_\_ Total Depth: 4030

I have this date completed supervision of plugging of:

Lease Name: Kuhn Well No. 1

Operator's Full Name: Kimbark Exploration Co

Complete Address: 201 University Bldg Denver, Colorado

Plugging Contractor Rocket Oil Well Service

Address: Box 7126 Denver, Colorado License No. \_\_\_\_\_

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD-Well \_\_\_\_\_ D & A x

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No x

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 2PM Day 11 Month 6 Year 62

The above well was plugged as follows:

8 5/8" 204' circulated with cement - 4 1/2" 4028' with 100 sax cement.

PB to 3920' perforated 3874' - filled with sand to 3860', set 3 sax cement

with dumpbailer, pulled 4 1/2" to 600', circulated hole with heavy gel

mud through 4 1/2" (15 sax Gel), displaced 20 sax cement through 4 1/2" at

600', heavy mud to 180', displaced 20 sax cement through 4 1/2" at 180',

heavy mud to 35', set bridge and cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED

6/20/62  
INV. NO. 5211-W