

KANSAS

Form CP-3  
Rev. 6-9-67

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 1 1967  
11-1-67

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address Box #797, Great Bend, Kansas.

Lease Name Mader Well No. 1

Location NE-NE-NW Sec. 7 Twp. 10 Rge. (E) (W)25

County Graham Total Depth 4242'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Above

Address      License No.     

Operation Completed: Hour 11:30PM Day 28 Month 10 Year 1967

The above well was plugged as follows:

211'--8 5/8" Surface pipe, cement circulated.  
Dakota section from 1025' to 850'.

Circulated hole with heavy mud, Pulled DP to 1050' and displaced 100 Sx. cement thru  
from 1050' to 730'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from 210'  
to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols  
Well Plugging Supervisor

DATE 11/1/67  
INV. NO. 6598-W