

15-065-20258-00-00

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 9 1969
 CONSERVATION DIVISION
 Wichita, Kansas

Operator's Full Name Executive Petroleum Company,
 Complete Address 1007 Denver U. S. National Center, Denver, Colorado.
 Lease Name McGuire Well No. 1
 Location S/2-NW-NE Sec. 7 Twp. 10 Rge. (E) (W) 25
 County Graham Total Depth 4030'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated
 Plugging Contractor L. J. Dreiling & Sons, Incorporated,
 Address R. R. #2, Victoria, Kansas. License No.
 Operation Completed: Hour 7:30 PM Day 6 Month 10 Year 1969

The above well was plugged as follows:

204'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1280' and displaced 100 Sx, cement thru
DP from 1280' to 955'. Pulled DP to 215' and displaced 20 Sx, cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx, cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
 DATE 10/9/69
 INV. NO. 622-44

Signed: M. L. Nichols
 Well Plugging Supervisor