

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 9 1967
8-9-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Kimbark Operating Company,

Complete Address: 288 Clayton Street, Denver, Colorado.

Lease Name William Well No. 1

Location NE-NW-SE Sec. 7 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4050

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Mirfin Drilling Company,

Address: 617 Union Center, Wichita, Kansas. License No. _____

Operation Completed: Hour 7:30PM Day 1 Month 8 Year 1967

The Above well was plugged as follows:

186'--8 5/8" Surface pipe, cement circulated with 165 Sx.
Dakota section from 1740' to 1926'.

Circulated hole with heavy mud, set plug thru DP from 1950' to 1650' with
100 Sx. cement. Pulled DP. to 180' and displaced 20 Sx. cement thru DP.
Pulled DP. set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. A. Nichols
Well Plugging Supervisor

INVOICED
DATE 8/9/67
INV. NO. 6107-40