

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NE NE NW

SEC. 11 TWP. 10 RGE. 25 ³⁰ ?

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Finley

Operator Empire Drg Co Address Wichita, Kans

Field _____ County Sheridan

Total Depth 4610 Feet.

Plugging Contractor same & Globe Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 224' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at

750', displaced 20 sax cement through drill pipe, heavy mud to

220', set cementing plug and displaced 20 sax cement through drill

pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and

10 sax cement to bottom cellar.

Edon Perry
District Conservation Agent

Date 11-21-57

RECEIVED
STATE CORPORATION COMMISSION

NOV 25 1957

CONSERVATION DIVISION
Wichita, Kansas

CP-3

PLUGGING
FILE SEC 11 T 10 R 25 SW
BOOK PAGE 63 LINE 22