

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Shields Oil Producers, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Baalman Well No. B-1

Location SW-SW-NW Sec. 12 Twp. 10 Rge. (E) (W) 30

County Sheridan Total Depth 4265'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Shields Drilling Company, Incorporated,

Address Shields Bldg., Russell, Kansas. License No.

Operation Completed: Hour 2:30 PM Day 15 Month 8 Year 1970

The above well was plugged as follows:

233'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 1325'.

Circulated hole with heavy mud, Pulled DP to 1550' and displaced 100 Sx. cement thru
DP from 1550' to 1225'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Dehok
Well Plugging Supervisor

INVOICED

DATE 8/17/70
INV. NO. 2404-W