

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don E. Pratt.
Complete Address Box #370, Hays, Kansas.
Lease Name F. Richmeier Well No. 1
Location SW-SW-SW Sec. 12 Twp. 10 Rge. (E) (W) 25
County Graham Total Depth 4050'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Dreiling Oil, Incorporated,
Address R. R. #2, Victoria, Kansas. License No.
Operation Completed: Hour 4:00 AM Day 16 Month 9 Year 1971

The above well was plugged as follows:

155'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement thru
DP from 1225' to 900'. Pulled DP to 185' and displaced 25 Sx. cement thru DP from
185' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 9-22-71

INV. NO. 4370-W