

15-065-20229-00-00

Form CP-3
Rev. 6-4-68

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 2 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum, Incorporated,

Complete Address 300 West Douglas, Wichita, Kansas.

Lease Name Herman Well No. H-1

Location CSE-NW Sec. 12 Twp. 10 Rge. (E) (W)25

County Graham Total Depth 4014'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Garvey Drilling Company,

Address Rte. #2, Great Bend, Kansas. License No.

Operation Completed: Hour 10:00 AM Day 31 Month 5 Year 1969

The above well was plugged as follows:

214'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement thru
DP from 1225' to 900'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 6/3/69
INV. NO. 9877-11