

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don E. Pratt Oil Operations,

Complete Address Drawer #370, Hays, Kansas. 67601

Lease Name Alice Knoll Well No. 1

Location SW-SE-NE Sec. 13 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 3744'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No. _____

Operation Completed: Hour 2:30 AM Day 5 Month 8 Year 1970

The above well was plugged as follows:

154'--8 5/8" Surface casing, cement circulated with 135 Sx.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1190' and displaced 100 Sx. cement thru
DP from 1190' to 865'. Pulled DP to 185' and displaced 25 Sx. cement thru DP from 185'
to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 8/10/70
INV. NO. 2348-W