

15-065-20605-00-06

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Billings Oil Company, - OIL PROPERTY MANAGEMENT, INC.

Complete Address 300 Insurance Building, Wichita, Kansas.

Lease Name Bollig Well No. 1

Location NE-NW-NW Sec. 17 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4000'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 8:30 AM Day 14 Month 5 Year 1973

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 110 Cu. Ft. cement
thru DP from 1175' to 850'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 5/16/73
INV. NO. 9369-W