

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

APR 13 1965  
04-13-65  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Rains and Williamson Oil Company,

Complete Address: 1425 Wichita Plaza, Wichita, Kansas.

Lease Name Brungardt Well No. 1

Location CNE-SW-NE Sec. 17 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4300

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 8:30PM Day 10 Month 4 Year 1965

The Above well was plugged as follows:

184'--8 5/8" Surface pipe, cement circulated with 135 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx. cement  
thru DP. Heavy mud to 180', set plug with 1/4 sack hulls and displaced 20 Sx.  
cement thru DP. Heavy mud to 40', set plug with 1/8 sack hulls and 10 Sx.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 4/13/65

INV. NO. 945-W