

15-065-20504-00-00 SP

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 17 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Brungardt Well No. 1

Location CSW-NW-SE Sec. 17 Twp. 10 Rge. (E) (W)25

County Graham Total Depth 4030' 50.38

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 9:00 PM Day 11 Month 1 Year 1972

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 110 Cu. Ft. cement  
thru DP from 1375' to 1050'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 1-18-72

INV. NO. 5075-11