

15-065-20086-00-00

Form CP-3
Rev. 6-26-62

KANSAS

al
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1967
9-21-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Petroleum, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name Brungardt Well No. E-1

Location CNE-NE Sec. 17 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 2950

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company,

Address: Rte. # 2, Great Bend, Kansas. License No.

Operation Completed: Hour 4:00AM Day 15 Month 9 Year 1967

The Above well was plugged as follows:

215'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Dakota Section from 1760' to 1570'.

Circulated hole with heavy mud, Pulled DP to 1792' and displaced 100 Sx. cement from
1792' to 1472'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from 240' to
180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*
Well Plugging Supervisor

DATE 9/21/67
INV. NO. 6364-11