

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1963
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Texaco Incorporated,
Complete Address: 614 Bitting Building, Wichita, Kansas.
Lease Name A. M. Knoll Well No. 1
Location CSE-SW Sec. 26 Twp. 10 Rge. (E) (W) 25
County Graham Total Depth 4409
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Glenn & Smith Pipe Pulling Inc.,
Address: 204 E. 6th, Ellinwood, Kansas. License No. 396
Operation Completed: Hour 6:00PM Day 5 Month 5 Year 1963

The Above well was plugged as follows:

258' -- 8 5/8" surface casing cement circulated w/165 Sx. 4090' 4 1/2"
production casing cemented w/125 Sx. Top plug back @ 2525'. Top
Perforations @ 2493', squeezed with 50 Sx cement.
Granded well back to 2480' and set 4 Sx cement w/ dump bailer. Pulled
4 1/2" casing to 550', circulated heavy gel mud (20 Sx.) and displaced 20
Sx cement thru casing. Pulled 4 1/2" casing to 240' and displaced 20 Sx
cement thru 4 1/2" casing. Pulled remainder of 4 1/2" casing, set bridge @
40' and 10 Sx cement to bottom of cellar. Recovered 2309' 4 1/2" casing.

(Mudding and cementing operations performed by Halliburton Oil Well
Cementing Co.,)

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/2/63
INV. NO. 7029-W

Signed: H. L. Nichols
Well Plugging Supervisor