

 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Chief Drilling Company, Incorporated.

Complete Address: Box #797, Great Bend, Kansas.

Lease Name Knoll Well No. 1

Location CSW-SW Sec. 26 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 3527'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 11:30 AM Day 12 Month 3 Year 1968

The Above well was plugged as follows:

205'--8 5/8" Surface pipe, cement circulated with 165 Sx.
Dakota section from 1020' to 1200'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement thru
DP from 1225' to 900'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from
210' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/15/68
INV. NO. 7419-u

Signed: 
Well Plugging Supervisor