

KANSAS

AL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 8 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address Box #797, Great Bend, Kansas.

Lease Name Knoll Well No. A-1

Location CSW-^{SE}~~SW~~ Sec. 26 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4040

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 6:30 PM Day 4 Month 4 Year 1968

The above well was plugged as follows:

210'--8 5/8" Surface pipe, cement circulated with 160 Sx.
Top of Dakota Section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pull DP to 215' and displaced 20 Sx. cement thru DP from 215'
to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar. (Cementing operations performed by Allied Cementing Company, Incorporated).

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Dehob*
Well Plugging Supervisor

INVOICED
DATE 4/8/68
INV. NO. 7536-W