

KANSAS

AL
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name National Oil Company.

Complete Address 200 West Douglas, Wichita, Kansas.

Lease Name Knoll Well No. 1

Location SW-NE-SE Sec. 26 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4070'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 10:30 AM Day 5 Month 9 Year 1971

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 210' and displaced 25 Sx. cement thru DP from
210' to 135'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 9-10-71

INV. NO. 4309-W