

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Mike Kelso Oil, Inc.
 Address: P.O. Box 467 Chase, Kansas 67524
 Phone: (620) 938-2943 Operator License #: 31528
 Type of Well: Oil Docket #: 31528
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: Virgil Clothier (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)

API Number: 15 - 053-20,018-00-00
 Lease Name: Phelan
 Well Number: 2
 Spot Location (QQQQ): C - E/2 - E/2 - SW
1320 Feet from North / South Section Line
1980 Feet from East / West Section Line
 Sec. 2 Twp. 17 S. R. 10 East West
 County: Ellsworth
 Date Well Completed: _____
 Plugging Commenced: 10-30-08
 Plugging Completed: 10-30-08

KCC
PKT
per
spot
research

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	257'	None
				5-1/2"	3290'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 3240' and 5 sacks cement. Perforated 5-1/2" casing @1250', 950' and 310'. Ran 2-3/8" tubing to 1250', pumped 35 sxs., cement, pulled up to 950', pumped 35 sxs. cement, pulled up to 310' and circulated 100 sxs. cement to surface, 60/40 pos, 4% gel. Plugging Complete.


Name of Plugging Contractor: Mikes' Testing & Salvage, Inc. License #: 31528
 Address: P.O. Box 467 Chase, Kansas 67524

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 05 2008
CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: Mike Kelso Oil, Inc.
 State of Kansas County, Rice, ss. Mike Kelso
 (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso
 (Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 31st day of October, 20 08
 My Commission Expires: _____
 Notary Public



PKT