

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Mike Kelso Oil, Inc.

Address: P.O. Box 467 Chase, Kansas 67524

Phone: (620) 562-7421

Operator License #: 31528

Type of Well: SWD

Docket #: D-25342

(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)

(If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top:	Bottom:	T.D.
_____	_____	_____
_____	_____	_____
_____	_____	_____

API Number: 15 - 053-00980-0001

Lease Name: Phelan

Well Number: 1

Spot Location (QQQQ): _____ - SW - NE - SW

1641

_____ Feet from ☐ North / ☒ South Section Line

3618 Feet from ☒ East / ☐ West Section Line

Sec. 2 Twp. 17 S. R. 10 ☐ East ☒ West

County: Ellsworth

Date Well Completed: _____

Plugging Commenced: 10-30-08

Plugging Completed: 10-30-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	264'	None
				5-1/2"	3280'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 3230' and 5 sxs. cement. Perforated 5-1/2" casing @1250', 950' & 315'. Ran 2-3/8" tubing to 1250', pumped 35 sxs. cement, pulled up tp 950', pumped 35 sxs. cement, pulled up to 315' and circulated 40 sxs. cement to surface.

60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc.

License #: 31528

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Mike Kelso Oil, Inc.

State of Kansas County, Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____


(Address) P.O. Box 467 Chase, Kansas

SUBSCRIBED and SWORN TO before me this 31st. day of October

20 08

My Commission Expires: _____

Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202