


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

SHERIDAN

County. Sec. 24 Twp. 10 Rge. 29 (E) (WEST)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines SE SE SE
Lease Owner EMPIRE DRILLING COMPANY
Lease Name KOERBER Well No. 1
Office Address 400 BROWN BLDG., WICHITA 2, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed NOVEMBER 1 1956
Application for plugging filed NOVEMBER 1 1956
Application for plugging approved NOVEMBER 5 1956
Plugging commenced NOVEMBER 1 1956
Plugging completed NOVEMBER 1 1956
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4539 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	221'	CEMENTED

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

BOTTOM PLUG SET AT 215' WITH 1/2 SACKS HULLS AND 15 SACKS CEMENT.
TOP PLUG SET AT 40' WITH 1/2 SACKS HULLS AND 10 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
11-10-1956

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY
Address 400 BROWN BLDG., WICHITA 2, KANSAS


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
I, DAN J. KORNFELD

(operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
DAN J. KORNFELD
400 BROWN BLDG., WICHITA 2, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 9TH day of NOVEMBER, 1956

Charlotte Stanley
Notary Public.



PLUGGING
FILE SEC. 24 T 10 R. 29w
BOOK PAGE 113 LINE 29

15-179-00167-00-00

LOG

COMPANY: EMPIRE DRILLING COMPANY, WICHITA, KANSAS

CONTRACTOR: EMPIRE DRILLING COMPANY, WICHITA, KANSAS

FARM: KOERBER NO. 1

LOCATION: SE SE SE OF SEC. 24-10-29W, SHERIDAN COUNTY, KANSAS

COMMENCED: OCTOBER 17, 1956

ELEVATION: 2771 K.B.

COMPLETED: NOVEMBER 1, 1956

0	TO	225	CLAY, SAND AND SHALE	TOPS:	
225	TO	1375	SHALE AND SAND		
1375	TO	2347	SHALE AND SHELLS	HOWARD	3634
2347	TO	2382	ANHYDRITE	TOPEKA	3661
2382	TO	2960	SHALE AND SHELLS	HEEBNER	3852
2960	TO	3600	SHALE AND LIME	TORONTO	3873
3600	TO	3830	LIME AND SHALE	LANSING K.C.	3890
3830	TO	3885	SHALE AND LIME	BASE K.C.	4148
3885	TO	4180	LIME	CHEROKEE	4358
4180	TO	4285	SHALE AND LIME	MISSISSIPPIAN	4462
4285	TO	4330	SHALE		
4330	TO	4435	SHALE AND LIME		
4435	TO	4507	LIME AND SHALE		
4507	TO	4534	LIME AND CHERT		
4534	TO	4539	CHERT		
4539			R.T.D.		

D & A

CASING RECORD: RAN 221' OF 8 5/8" AND CEMENTED WITH 125 SACKS CEMENT

RAN SCHLUMBERGER ELECTRIC LOG

CERTIFICATION

I, DAN J. KORNFIELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE KOERBER NO. 1, SE SE SE OF SEC. 24-10-29W, SHERIDAN COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
DAN J. KORNFIELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 9TH DAY OF NOVEMBER, 1956.

Charlotte Stanley
NOTARY PUBLIC

Notary Commission Expires June 7, 1960

PLUGGING
FILE SEC. 24 T. 10 R. 29W
BOOK PAGE 113 LINE 29

RECEIVED
NOV 10 1956