


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Sheridan County, Sec. 24 Twp. 10S Rge. (E) 29 (W)

Location as "NE/CNW%SW%" or footage from lines NW NW SE
Lease Owner Braden Drilling, Inc.
Lease Name Koerber Well No. 1-24
Office Address 1620 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 28, 1968
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced October 28, 1968
Plugging completed October 28, 1968
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Leo Massey of Hays)



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4190 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	281'	8-5/8"	10/20/68	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from Total Depth to 1500 Feet;
Plug and 70 sax Cement thru the Drill Pipe;
Mud to 280 Feet; Plug and 20 sax Cement thru the Drill Pipe; Mud to 40 Feet;
Plug bridged with Kelly and 20 sax Cement to Base of Cellar; 2 sax Cement in Rat Hole.
Job completed @ 9:30 P.M. on 10/28/68.

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1968
CONSERVATION DIVISION
Wichita, Kansas


11-1-1968

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
T. M. McCaul, Jr. of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
500 Bitting Building, Wichita, Kansas
(Address)



Subscribed and sworn to before me this 31st day of October, 1968

Louise K. Whitted
Louise K. Whitted Notary Public.

My commission expires November 26, 1970.

15-179-20152-00-00

DRILLERS LOG

KOERBER NO. 1-24

CASING RECORD:	OPERATOR: Braden Drilling, Inc.	DESCRIPTION:
8-5/8" @ 281' w/185 sax Cement	CONTRACTOR: Sage Drilling Co., Inc.	NW NW 1/4 Sec. 24-10S-29W Sheridan County, Kansas
TOTAL DEPTH: 4190'	COMMENCED: October 19, 1968	
	COMPLETED: October 28, 1968	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	130	
Blue Shale	130	290	
Shale	290	955	
Shale & Shells	955	1859	
Shale & Sand	1859	1890	
Shale	1890	2046	
Sand	2046	2180	
Shale & Shells	2180	2370	
Anhydrite	2370	2415	
Shale & Lime	2415	2525	
Lime & Shale	2525	2750	
Shale & Lime	2750	3017	
Lime & Shale	3017	3946	
Lime	3946	4140	
Lime & Shale	4140	4190	D&A

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1968
CONSERVATION DIVISION
Wichita, Kansas

11-1-1968

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

T. M. McCaul, Jr.
By _____
T. M. McCaul, Jr.



Subscribed and sworn to before me this 31st day of October, 1968.

Louise K. Whitted

Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.