

15-179-20408-00-00

FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

WELL PLUGGING RECORD

Sheridan County, Sec. 20 Twp. 10S Rge. 30W (E) (W)

Location as "NE/CNW&SW" or footage from lines SW SW 660' FSL & FWL

Lease Owner APCO OIL CORPORATION

Lease Name Ben Hemmert Well No. 1

Office Address 1700 HNG Bldg., Houston, Texas 77002

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-16 19 75

Application for plugging filed 8-19 19 75

Application for plugging approved -- 19


Plugging commenced 8-16 19 75

Plugging completed 8-16 19 75

Reason for abandonment of well or producing formation Dry well

If a producing well is abandoned, date of last production NA 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plot

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor

Producing formation None Depth to top Bottom Total Depth of Well 4645 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Rows include Topeka, Heebner, Toronto, Lansing, Pawnee, Fort Scott, Cherokee, and Mississippi.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

70 sx cement plug w/50/50 POS, 6% gel from 1025' to 1300'.
20 sx cement plug from 185' to 275'.
10 sx cement plug from 0 to 40'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Company

Address Hays, Kansas

STATE OF TEXAS COUNTY OF HARRIS ss. A. K. Gideons

(employee or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. K. Gideons A. K. Gideons

1700 HNG Bldg., Houston, Texas 77002 (Address)

Subscribed and Sworn to before me this 22nd day of August, 19 75

Notary Public. Donna Christensen



RECEIVED STATE CORPORATION COMMISSION

AUG 25 1975 08-25-1975 CONSERVATION DIVISION Wichita, Kansas

CONTRACTOR'S WELL LOG

15-179-20408-00-00

OPERATOR:	Apco Oil Corporation
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	BEN HEMMERT #1
LOCATION:	SW SW Section 20-10S-30W Sheridan County, Kansas
SPUD DATE:	August 6, 1975
COMPLETION DATE:	August 16, 1975

0	220	Surface Dirt & Sand
220	310	Shale
310	723	Sand & Shale
723	2360	Shale & Sand
2360	2485	Shale
2485	2535	Anhydrite
2535	3070	Shale
3070	3660	Shale & Lime
3660	3922	Lime & Shale
3922	4645	Lime
	4645	Rotary Total Depth

Spud @ 9:30 a.m. August 6, 1975. Drilled 310' of 12 1/2" surface hole. Ran 8 jts. 8 5/8", set @310'. Cemented with 300 sx. Common, 4% gel, 3% calcium chloride. Cement circulated. Plug was down @ 8:30 p.m., August 6, 1975.
 Plugged and Abandoned: 1st Plug Set @ 1300' with 70 Sacks; 2nd Plug Set @ 310' with 20 Sacks; 3rd Plug Set @ 40' with 10 Sacks; Plug was down @ 2:30 p.m., August 16, 1975. State Pluggor: Gilbert Balthazor

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack K. Wharton, Geologist of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the BEN HEMMERT #1, SW SW, Section 20-10S-30W, Sheridan County, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

ABERCROMBIE DRILLING, INC.

AUG 21 1975
 08-21-1975
 CORPORATION DIVISION
 Wichita, Kansas

By: Jack K. Wharton
 Jack K. Wharton-Geologist

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 20th day of August, 1975.

Nancy E. Haner
 Nancy E. Haner-Notary Public

