


15-179-20561-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sheridan County, Sec. 15 Twp. 10S Rge. 30 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SW SW
Lease Owner K & E Petroleum, Inc.
Lease Name DICKMAN Well No. 1
Office Address 816 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed 07-09 1980
Application for plugging filed 07-09 1980
Application for plugging approved 07-09 1980
Plugging commenced 07-09 1980
Plugging completed 07-09 1980

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 4588'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 4588'
Set 1st plug at 1300' with 70 sx.
2nd plug at 260' with 20 sx.
3rd plug at 40' solid bridge with 10 sx.
Rathole with 5 sx. 50/50 posmix, 6% gel. Cement
by Sun Cementing. State plugger Gilbert Balthazor.
Plug was down at 5:00 p.m. 07-09-80.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
-801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 1980

My commission expires



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.



15-179-20561-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	K & E Petroleum, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	DICKMAN #1
LOCATION:	C SW SW, Section 15-10S-30W Sheridan County, Kansas
SPUD DATE:	07-03-80
COMPLETION DATE:	07-09-80

0	40	Surface Clay
40	2465	Shale & Sand
2465	2502	Anhydrite
2502	3000	Shale
3000	3800	Shale & Lime
3800	4003	Lime & Shale
4003	4588	Lime
	4588	Rotary Total Depth

Spud hole at 5:30 p.m. 07-03-80. Drilled 286' in a 12-1/2" hole. Ran 7 joints of 8-5/8" new 20# casing (tally 277'). Set at 284' KB with 230 sx of common cement, 2% gel, 3% c.c. Cement did circulate. Plug was down at 10:30 p.m. 07-03-80.

T.D. 4588'. 1st plug set at 1300' with 70 sx. 2nd plug set at 260' with 20 sx. 3rd plug set at 40', solid bridge with 10 sx. Rathole with 5 sx. 50/50 posmix, 6% gel. Plug was down at 5:00 p.m. 07-09-80.

SAMPLE TOPS:

Anhydrite	2465'
B/Anhydrite	2502'

RECEIVED
STATE CORPORATION COMMISSION
07-18-1980
JUL 18 1980
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the DICKMAN #1, C SW SW, Section 15-10S-30W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state and of this 15th day of July, 1980.

Sherrie L. Brooks
Sherrie L. Brooks, Notary Public

