

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-179-20386-00-01

LEASE NAME Dickman #1-15

WELL NUMBER #1-15

SPOT LOCATION NE-NE-SW

SEC. 15 TWP. 10S RGE. 30 W or (W)

COUNTY Sheridan

Date Well Completed 9/4/87

Plugging Commenced 10/28/87

Plugging Completed 10/29/87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300 Wichita, Ks 67202

PHONE # (316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Lansing/Kansas City Depth to top 4179 bottom 4218

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing/Kans City	Oil & Wtr	4179	83	8 5/8	272	-0-
Lansing/Kans City	Oil & Wtr	4214	18	4 1/2	4279	1442

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Spotted sand across perforations with top of sand @ 4125'. Spotted 4 sx cmt on top of sand with dump bailer. Shot csg off @ 1442'. Halliburton pumped 500# hulls followed by 200 sx Hays District Light Cmt dwn 8 5/8" surface csg. Plug from surface to 2025'. Max press 300 psig. ISIP = 200 psig. Well plugged @ 9:00 AM.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347, Chase, Ks 67524

STATE OF Kansas COUNTY OF Sedgwick, ss.

Lanny Butner, Western Div., Prod. Mgr. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) By: Lanny Butner

(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 11 day of Nov., 1987



Kerran Redington  
Notary Public  
Kerran Redington

My Commission expires: 2/6/90