

15-179-00174-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Sheridan County. Sec. 7 Twp. 10S Rge. 26 (X) W (W)

Location as "NE/CNW%SW%" or footage from lines C. SE/4 SE/4

Lease Owner Heathman-Seeligson Drilling Co.

Lease Name KAISER Well No. 1

Office Address 1015 E. Second, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-9- 19 56

Application for plugging filed 12-9- 19 56

Application for plugging approved 12-9- 19 56

Plugging commenced 12-9- 19 56

Plugging completed 12-9- 19 56

Reason for abandonment of well or producing formation Dry and Abandoned

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4513 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8" used csg.		
				cemented at 236.68'		
				w/175 sx. cement &		
				2 Calcium Chloride.		
				Cement Circulated.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

**Filled hole to 240' w/mud. Set bottom plug and 1/2 sacks hulls and 15 sacks cement. Set top plug at 40' w/1/2 sack hulls and 10 sacks cement.**

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Heathman-Seeligson Drilling Co.

Address 1015 E. Second, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.


H. D. Shreve (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) By: [Signature]

1015 E. Second, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of December, 19 56

Patricia W. Lankin  
Patricia W. Lankin Notary Public.



DEC 27 1956  
12-27-56  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 7.T.10 R26W  
BOOK PAGE 126 LINE 25

DRILLERS' LOG

<b>NAME:</b>	KAISER #1	<b>DATE SPUN:</b>	11-28-56
<b>LOCATION:</b>	C. SE/4 SE/4 Sec. 7-108-26W Sheridan County, Kansas	<b>ROTARY COMPLETED:</b>	12-9-56
<b>OPERATOR:</b>	Heathman-Seeligson Drilling Co.	<b>ELEVATION:</b>	2645 GR 2647 DF 2650 KB
<b>CONTRACTOR:</b>	Heathman-Seeligson Drilling Co.	<b>ROTARY TOTAL DEPTH:</b>	4513'
<b>SURFACE CASING:</b>	Ran 12 jts. of 8-5/8" used casing cemented at 236.68' with 175 sacks of sack cement and 2 Calcium Chloride. Cement Circulated.		
<b>OIL STRING:</b>	None run - Dry and abandoned 12-9-56		

DRILL STEM TESTS

#1 3915-31 open 1 hr., rec. 3' oil, 17' oil cut mud. FBHP-345# in 20 min.  
#2 3937-62 open 1 hr., rec. 41' very slightly oil specked salt water. IBHP-1620, IFP-25, FFP-30, FBHP-440 in 20 min.

GEOLOGICAL TOPS (KS)

Howard	3637 (-987)
Topeka	3865 (-1015)
Heebnor	3855 (-1205)
Toronto	3877 (-1227)
Lansing	3893 (-1243)
Base K.C.	4130 (-1480)
Marmaton	4164 (-1514)
Cherokee	4341 (-1691)
Miss. Chert	4451 (-1801)
R.T.D.	4513'

LOG

(Figures indicate bottom of formation)


Clay & Sand	0 - 100
Sand	230
Shale	242
Shale, Shells & Sand	1300
Shale & Shells	1755
Blain Anhydrite	1790
Shale & Red Bed	2280
Anhydrite	2320
Shale & Shells	2520
Shale & Lime	3300
Lime	3380
Lime & Shale	3045
Lime	4150
Lime & Shale	4450
Lime	4485
Lime, Shale & Chert	4513

The undersigned, H. D. Shreve, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Report.

HEATHMAN-SEELIGSON DRILLING CO.

By: 

Subscribed and sworn to before me the 26th day of December, 1956.

  
Patricia W. Lanekin, Notary Public

My commission expires: April 3, 1960

PLUGGING  
FILE SEC. 7, T. 10, R. 26, W.  
BOOK PAGE 126 LINE 25