

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-179-21,043-00-00

LEASE NAME Kaiser

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1-8

330' Ft. from S Section Line

990' Ft. from E Section Line

LEASE OPERATOR Rine Drilling & Exploration, Inc.

SEC. 8 TWP. 10S RGE. 26 (E) or (W)

ADDRESS 200 W. Douglas, Suite 1050, Wichita, KS 67202-3010 COUNTY Sheridan

PHONE# (316) 262-5418 OPERATORS LICENSE NO. 5654

Date Well Completed _____

Character of Well D&A

Plugging Commenced 7-29-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-30-92

The plugging proposal was approved on 7-30-92 (date)

by Dennis Hamil (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation Lansing-Kansas City Depth to Top _____ Bottom _____ T.D. 4160

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	263'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Fill w/heavy mud; set 1st plug @ 2270'-2170' w/25 sx; 2nd plug @ 1340'-940' w/100 sx; 3rd plug @ 280'-120' w/40 sx; 4th plug @ 40'-surface w/10 sx; mousehole 10 sx; rathole 15 sx; 60-40 posmix 6% gel 1/4# Floccel per sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rine Drilling & Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 31st day of August 1992

Angela Woodard Notary Public
 RECEIVED STATE CORPORATION COMMISSION
 8-3-92
 AUG 3 1992

My Commission Expires: 3-20-93

ORIGINAL

15-079-21043-0000



RINE DRILLING AND EXPLORATION, INC.

SUITE 1050 - 200 W. DOUGLAS — WICHITA, KANSAS 67202-3010
316/267-1333 FAX 316/262-5472

AC0-1 Attachment

Re: Drill Stem Tests
#1-8 Kaiser
Tilton N.E. Revival
SE SW SW
Section 8-10S-26W
Sheridan County, Kansas

DST #1: 3880'-3905' (Lansing B&C)
30-60-15-45
Wk blow in 1st open.
No blow in 2nd open.
Rec. 25' oil stained mud.
IFP: 50-50 ISIP: 976
FFP: 71-71 FSIP: 926

DST #2: 3914'-3961' (Lansing E&F)
30-60-30-60
Strong blow in both opens.
Rec. 1370' water
IFP: 101-365 ISIP: 1055
FFP: 447-617 FSIP: 1045

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1992

CONSERVATION DIVISION
Wichita, Kansas