

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-179-20,947-00-00

LEASE NAME Martin "B"

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

2310 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 8 TWP. 10S RGE. 26 ~~XXXX~~ (W)

COUNTY Sheridan

LEASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS P. O. Box 780407, Wichita, KS 67278

PHONE# (316) 685-1441 OPERATORS LICENSE NO. 5131

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 7-25-89

Plugging Commenced 7-25-89

Plugging Completed 7-26-89

The plugging proposal was approved on 7-26-89 (date)

by State plugger, Gib Schenk (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	256'	None

RECEIVED  
STATE CORPORATION COMMISSION  
8-18-89

AUG 18 1989  
8-18-89

CONSERVATION DIVISION  
Wichita Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Circulate heavy mud in hole. 1st plug from 2250' to 2170' w/20 sx. 2nd plug from 1350' to 950' w/100 sx. and 1 sack Flocel. 3rd plug from 300' to 140' w/40 sx. 4th plug from 40' to surface w/10 sx. and wiper plug. Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thunderbird Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 17th day of August, 1989

Sharan J. Branstetter Notary Public  
Commission Expires: May 18, 1993

