

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-179-210790000

LEASE NAME Werth

WELL NUMBER 15-33

1050 Ft. from S Section Line

2200 Ft. from E Section Line

SEC. 15 TWP. 10 RGE. 26 ~~W~~ (W)

COUNTY Sheridan

Date Well Completed 12-3-95

Plugging Commenced 12-3-95

Plugging Completed 12-3-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR L. B. Industries, Inc.

ADDRESS 12200 E. Briarwood Ave. - #250

Englewood, CO 80112-6702

PHONE# (303) 790-8340 OPERATORS LICENSE NO. 3680

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 3, 1995 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4505'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS.

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	335'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Spotted 25 sx. cement at 2225' thru drill pipe. Spotted 100 sx. cement at 1250' thru drill pipe. Spotted 40 sx. cement at 375' thru drill pipe. Spotted 10 sx. cement at 40' thru drill pipe. 15 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address P. O. Box 48848, Wichita, KS 67201-8848


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. B. Industries, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael L. Considine

(Address) P. O. Box 48848
Wichita, KS 67201-8848




RECEIVED
STATE CORPORATION COMMISSION
12-15-95

AND SWORN TO before me this 6th day of December, 19 95

Carolyn J. Tjaden
Notary Public

My Commission Expires: September 5, 1996 Carolyn J. Tjaden

CP4



ORIGINAL

WHITE

CONFIDENTIAL

AND ELLIS DRILLING, Inc.

RELEASED

DRILLERS LOG

15-179-21079-0000

FEB 6 1997

Operator: **L. B. Industries, Inc.**
12200 E. Briarwood Avenue - #250
Englewood, CO 80112

KCC

DEC 13

CONFIDENTIAL

Contractor: **White & Ellis Drilling, Inc.**
P. O. Box 48848
Wichita, KS 67201-8848

Lease Name Werth Well No. 15-33
Spot App. NW SW SE Section 15 Township 10S Range 26W
County Sheridan State Kansas

Casing Record:

Surface: 8 5/8" @ 335' with 225
Production: _____ @ _____ with _____

Type Well: D & A Total Depth 4505'

Drilling Commenced: 11-24-95 Drilling Completed: 12-3-95

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Tops</u>
Cellar	0	5	Heebner/Toronto
Clay & Shale	5	336	& Lansing 3755
Shales, Clay & Sand	336	865	Lansing 3897
Shale, Sand & Lime	865	1505	Kansas City 3985
Shale, Sand, Red Bed & Lime	1505	2450	Marmaton/ Pawnee/ Ft. Scott 4155
Shale, Sand & Lime	2450	2760	Ft. Scott/Cherokee 4285
Lime & Shale	2760	3250	Ft. Scott 4350
Shale & Lime	3250	3430	Cherokee/Ft. Scott 4450
Lime & Shale	3430	4505	

DEC 15 1995

CONSERVATION DIVISION
WICHITA, KANSAS

CONFIDENTIAL

DST DATA

ORIGINAL

15-179-21079-0000

Werth #15-33
Section 15, T10S, R26W
Sheridan County, Kansas

DST #1 @ 3878'-3897'; 30"-45"-45"-60"; Rec 1 ft mud; IHP 1846, IFP 27-28, ISIP 32, FFP 27-27, FSIP 31, FHP 1828, BHT 111°F.

DST #2 @ 3898'-3924'; 30"-45"-30"-45"; Rec 1 ft mud; IHP 1848, IFP 30-30, ISIP 37, FFP 29-29, FSIP 35, FHP 1837, BHT 112°F.

DST #3 @ 3980'-4035'; 30"-45"-30"-45"; Rec 5 ft mud with specks oil; IHP 1928, IFP 31-33, ISIP 888, FFP 33-34, FSIP 794, FHP 1826, BHT 113°F.

DST #4 @ 4040'-4080'; 30"-45"-30"-45"; Rec 15 ft mud with show oil; IHP 1992, IFP 31-31, ISIP 1271, FFP 31-31, FSIP 1160, FHP 1922, BHT 113°F.

DST #5 @ 4300'-4350'; 30"-30"-30"-30"; Rec 1 ft mud; IHP 2203, IFP 0-0, ISIP 0, FFP 20-20, FSIP 30, FHP 2173, BHT 113°F.

KCC

DEC 13

CONFIDENTIAL

RELEASED

FEB 6 1997

FROM CONFIDENTIAL

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1995

WICHITA, KANSAS