

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Sheridan SEC. 15 TWP. 10S RGE. 26W E/W  
Location as in quarters or footage from lines:  
SW SW NW


Lease Owner Gerald Befort  
 Lease Name Werth ~~H~~ H Well No. 1 AWB  
ECC  
 Office Address 1105 East 30th Hays, Kansas 67601  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 5-18-82  
 Plugging completed 5-19-82  
 Reason for abandonment of well or producing formation \_\_\_\_\_  
 \_\_\_\_\_ Depleted

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3936'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	209'	none
				4-1/2"	3935'	1819'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 3800' and ran 4 sacks cement. Shot casing @2518',  
2312', 2000' and 1832'. Pulled a total of 45 joints of 4-1/2" casing. Plugged well  
with 5 sacks hulls, 25 sacks gel, 60 sacks cement, 15 sacks gel, 70 sacks cement,  
8-5/8" plug, 10 sacks cement.

Plugging complete. **RECEIVED**  
STATE CORPORATION COMMISSION  
MAY 24 1982

**CONSERVATION DIVISION**  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 176 Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of May, 19 82

Irene Hoover  
Notary Public.

My Commission expires:

