

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-193-20,607-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Argent Energy, Inc. KCC LICENSE # 30269
(owner/company name) (operator's)

ADDRESS 100 S. Main, Suite 510 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-5111

LEASE Albers WELL# 1 SEC. 6 T. 10S R. 31 (East/West) West

N/2 - SW - NE - SPOT LOCATION/QQQQ COUNTY Thomas

1650' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1980' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 279' CEMENTED WITH 60-40 posmix-200 sx SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 3077'/3082' T.D. 4722' PSTD _____ ANHYDRITE DEPTH 2637'-2663'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2660' w/25 sx; wnd plug @

1575' w/100 sx; 3rd plug @ 320' w/40 sx; 4th plug @ 40' w/10 sx w/wiper plug; rathole 15
sx; Total 190 sx 60-40 posmix 6% gel 1/4# Floccel per sx.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? No

If not explain why? Sent to Operator to complete.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE# (316) 674-5763

ADDRESS 216 E. McFarland City/State Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684
(company name) (contractor's)

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 8:00 a.m. 2-1-93

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2-22-93 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

RECEIVED
STATE CORPORATION COMMISSION
FEB 23 1993
02-23-1993
CONSERVATION DIVISION
Wichita, Kansas