

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 129-30099 - 00 - 00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____

Well Operator: Clipper Energy, LLC KCC License #: 33979
(Owner / Company Name) (Operator's)

Address: 3838 Oak Lawn, Suite 1310 City: Dallas

State: Texas Zip Code: 75219 Contact Phone: (214) 220 - 1080

Lease: USA Gas Unit 'D' Well #: 2 Sec. 29 Twp. 34 S. R. 43 East West

C - NE - SW Spot Location / QQQQ County: Morton

1980 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

3300 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 33' Cemented with: 2 yards Ready Mix Sacks

Production Casing Size: 4-1/2", 9.5#, J55 Set at: 1349' Cemented with: 550 Sacks

List (ALL) Perforations and Bridgeplug Sets: 1230'-34' (16 holes) & 1248'-52' (16 holes)

Elevation: 3510' (G.L. / K.B.) T.D.: 1350' PBDT: 1299' Anhydrite Depth: 1202'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Spot +/-100 sx 60/40 Pozmix, 4% gel, w/ 500# cotton seed hulls,
f/ PBDT @ 1299' to surface. Cut off casing 5' below ground level and weld on cap.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Jay Pulte

Phone: (214) 220 - 1080

Address: 3838 Oak Lawn, Suite 1310 City / State: Dallas, Texas 75219

Plugging Contractor: Allied Cementing Company, Inc. KCC License #: 99996
(Company Name) (Contractor's)

Address: P.O. Box 830 Liberal, KS. 67901 Phone: (620) 624 - 5937

Proposed Date and Hour of Plugging (if known?): To be determined.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11/4/08 Authorized Operator / Agent: Jay Pulte (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 17 2008

CONSERVATION DIVISION
WICHITA, KS

Dist 1
PKT



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

CLIPPER ENERGY LLC
TWO TURTLE CRK
3838 OAK LAWN
DALLAS, TX 75219-4520

November 21, 2008

Re: USA GAS UNIT D #2
API 15-129-30099-00-00
29-34S-43W, 1980 FSL 1980 FWL
MORTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after May 20, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888