

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-163-21,222 -00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 1-08-1981 original dt.

Well Operator: Gene Karlin Company KCC License #: 03444
(Owner / Company Name) (Operator's)

Address: 1111 Oakmont City: Hays

State: Kansas Zip Code: 67601 Contact Phone: (785) 623-1083

Lease: Veverka Well #: 2 Sec. 6 Twp. 9 S. R. 18 ☐ East ☒ West

NW - SE - SW Spot Location / QQQQ County: Rooks

990 Feet (in exact footage) From ☐ North / ☒ South (from nearest outside section corner) Line of Section (Not Lease Line)

3630 Feet (in exact footage) From ☒ East / ☐ West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: ☐ Oil Well ☐ Gas Well ☐ D&A ☐ Cathodic ☐ Water Supply Well
☒ SWD Docket # 0-20,105 ☐ ENHR Docket # ☐ Other:

Conductor Casing Size: none Set at: Cemented with: Sacks

Surface Casing Size: 8-5/8" Set at: 275' Cemented with: 175 Sacks

Production Casing Size: 4-1/2" Set at: 3530' Cemented with: 825 Sacks

List (ALL) Perforations and Bridgeplug Sets:

Elevation: 2049 (☐ G.L. / ☒ K.B.) T.D.: PBTD: 1765' Anhydrite Depth: 1467
(Stone Corral Formation)

Condition of Well: ☐ Good ☐ Poor ☐ Casing Leak ☒ Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Tried pulling 2" duraline tubing. Parted on 57th joint @ 1765'. Run 2" tubing to bottom. Spot cement on bottom and fill casing with cement. Pull tubing. Check for hole between 4-1/2" and 8-5/8".

Is Well Log attached to this application as required? ☒ Yes ☐ No Is ACO-1 filed? ☒ Yes ☐ No

If not explain why?

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 18 2008

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.
CONSERVATION DIVISION

List Name of Company Representative authorized to be in charge of plugging operations: Gene Karlin

Phone: (785) 623-1083

Address: 1111 Oakmont City / State: Hays, Kansas 67601

Plugging Contractor: Allied Cementing Company KCC License #: 99996 PRT KCC
(Company Name) (Contractor's)

Address: P.O. Box 31, Russell, Kansas 67665 Phone: (785) 483-2627

Proposed Date and Hour of Plugging (if known?): A.S.A.P.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11-15-2008 Authorized Operator / Agent: Gene Karlin
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dist 4
PRT

FRONTIER OIL CO.
 1720 KSB&T BLDG. #2 VEVERKA *SWD* 6-9-18W
 WICHITA, KS 67202 NW SE SW
 CONTR RED TIGER DRILLING CO. CTY ROOKS
 GEOL RICHARD D. PARKER FIELD BARRY SE
 2049 KB CM 1/8/81 CARD ISSUED 3/26/81 SWDW
 ARB 3483-90

+	+
+	+
+	+
+	+

API 15-163-21,222

SMP	TOP	DEPTH	DATUM
ANH	1467	+ 582	
BRNVILE	2717	- 658	
TARK	2808	- 759	
HOW	2958	- 909	
TOP	2990	- 941	
HEEB	3200	- 1151	
TOR	3222	- 1173	
LKC	3243	- 1194	
B KC	3459	- 1410	
ARB	3485	- 1436	
RTD	3750	- 1701	
NO LOG			

B-5/8" 272/175sx, 4 1/2" 3530/275sx
 DST (1) 3124-3182 (TOP)/60-30-50-30,
 REC 190' MSW, SIP 952-932#, FP
 42-93/93-124#
 DST (2) 3196-3360 (FOR, LKC)/60-30-60-
 30, REC 64' WM, SIP 560-560#, FP
 110-110/110-110#
 DST (3) 3342-3460 (LKC)/60-30-0-0,
 REC 20' M, ISIF 228#, IFP 41-62#
 DST (4) 3420-3488 (B KC, PENN, ARB)/
 60-30-0-0, REC 62' M, ISIF 394#,
 IFP 83-104#

8

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(OVER)

RECEIVED
 KANSAS CORPORATION COMMISSION

NOV 18 2008

CONSERVATION DIVISION
 WICHITA, KS

FRONTIER OIL CO. #2 VEVERKA *SWD* 6-9-18W
 NW SE SW

DST (5) 3420-3490 (B KC, PENN, ARB)/
 60-30-60-30, REC 10' OCM, 180'
 WM, SIP 597-545#, FP 63-94/94-105#
 MICT - CO, PF (ARB) 4/3483-88, AC 250
 G (15%), SWB DWN & SWB DRY/1HR, PF
 (ARB) 4/3488-90, AC 500 G (15%),
 SWB 1 BWPH, SWDW - INJECTION RATE
 130 BWPH



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

KARLIN, GENE DBA GENE KARLIN COMPANY
1111 OAKMONT ST
HAYS, KS 67601-1823

November 21, 2008

Re: VEVERKA #2
API 15-163-21222-00-01
6-9S-18W, 990 FSL 3630 FEL
ROOKS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after May 20, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550