

original  
RECEIVED

JUL 18 2005

KCC WICHITA

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form ACO-1  
September 1999  
Form Must Be Typed

WELL COMPLETION FORM  
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Operator: License # 33608  
Name: W.D. Short Oil Co., LLC  
Address: P O Box 729 - 102 S. River Rd  
City/State/Zip: Oxford, KS 67119  
Purchaser:  
Operator Contact Person: William D. Short, Jr.  
Phone: (620) 455-3576  
Contractor: Name: Berentz Drilling Company, Inc.  
License: 5892  
Wellsite Geologist: Joe Baker

Designate Type of Completion:  
 New Well  Re-Entry  Workover  
 Oil  SWD  SLOW  Temp. Abd.  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator:  
Well Name:

Original Comp. Date: Original Total Depth:  
 Deepening  Re-perf.  Conv. to Enhr./SWD  
 Plug Back  Plug Back Total Depth  
 Commingled  Docket No.  
 Dual Completion  Docket No.  
 Other (SWD or Enhr.?)  Docket No.

1-09-04 1-18-04 6-29-05  
Spud Date or Date Reached TD Completion Date or  
Recompletion Date Recompletion Date

API No. 15 - 035-24191-00-00  
County: Cowley  
C - NW Sec. 21 Twp. 33 S. R. 3  East  West  
3960 feet from S N (circle one) Line of Section  
3960 feet from E W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE SE NW SW

Lease Name: M Short Well #: 1  
Field Name: Rainbow Bend

Producing Formation: Bartlesville

Elevation: Ground: 1120' Kelly Bushing:

Total Depth: 3778' Plug Back Total Depth:

Amount of Surface Pipe Set and Cemented at 236' Feet

Multiple Stage Cementing Collar Used?  Yes  No

If yes, show depth set Feet

If Alternate II completion, cement circulated from  
feet depth to w/ sx cmt.

Drilling Fluid Management Plan AH 1 ncl 8-11-08  
(Data must be collected from the Reserve Pit)

Chloride content 900 ppm Fluid volume 500 bbls

Dewatering method used Hauled fluids from reserve & mud to Nelson A-2

Location of fluid disposal if hauled offsite:

Operator Name: W.D. Short Oil Co., LLC

Lease Name: License No.: 33608

Quarter Sec. Twp. S. R.  East  West

County: Cowley Docket No.:

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: *William D. Short*

Title: Resident Agent Date: 7-7-05

Subscribed and sworn to before me this 7th day of July

20 05 Notary Public: *Denese A. Wilson*

Date Commission Expires: 3-30-09

**KCC Office Use ONLY**  
*KCO* Letter of Confidentiality Received  
If Denied, Yes  Date:  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution

**DENESE A. WILSON**  
Notary Public - State of Kansas  
My Appt. Expires 3-30-09



# United Cementing and Acid Co., Inc.

SERVICE TICKET

5083

ORIGINAL

Oil Well Cementing & Acidizing  
 (316) 321-4680 • 800-794-0187 • FAX (316) 321-4720  
 2510 West 6th Street • El Dorado, KS 67042

DATE 1-17-04

COUNTY Cowley CITY \_\_\_\_\_

CHARGE TO W.D. Short

ADDRESS \_\_\_\_\_ CITY \_\_\_\_\_ ST \_\_\_\_\_ ZIP \_\_\_\_\_

LEASE & WELL NO. M. Short CONTRACTOR Berentz Drilling Co.

KIND OF JOB PRODUCTION CASINGS SEC. 21 TWP. 33 RNG. 3E

DIR. TO LOC. OXFORD 75-3E OLD  NEW

Quantity	MATERIAL USED	3776	Serv. Charge	
200SX	60/40 poz. 2% gel + 10% salt + 5# Kol-Seal			998.00 ✓
45X	gel @ 9.79			980.00 ✓
20SX	salt 1000lbs @ 9.50 cwt.			38.80 ✓
1000lbs	Kol-Seal @ 4.00			95.00 ✓
4	centerlizers 5 1/2 @ 32.00			400.00 ✓
1	Basket 5 1/2		119.00	128.00 ✓
234SX	BULK CHARGE			<del>119.00</del>
.58	BULK TRK. MILES 11.70 tons			229.32 ✓
.58	PUMP TRK. MILES			495.37 ✓
1	Guide shoe 5 1/2 - 1-5 1/2 AFU INSERT			118.90 ✓
1	PLUGS Top Rubber 5 1/2			274.00 ✓
		.0530	SALES TAX	51.00 ✓
			TOTAL	148.90

T.D. 3778  
 SIZE HOLE 7 7/8  
 MAX. PRESS. 1300  
 PLUG DEPTH 3776  
 PLUG USED TOP RUBBER

CSG. SET AT 3776 VOLUME 4076.35  
 TBG SET AT \_\_\_\_\_ VOLUME RECEIVED  
 SIZE PIPE 5 1/2"  
 PKER DEPTH \_\_\_\_\_  
 TIME FINISHED 9:30 **KCC WICHITA**

REMARKS: RAN 5 1/2 CSG TO 3778 TAG BOTTOM PICK UP 2' + SET - BREAK CIRCULATION  
MIX 1/2 Pump 200SX (60/40 poz 2% GEL, 10% SALT, 5# Kol-Seal) 1SX - Wash out Pump 1/2  
LINE - START DISP. 5BPM/150# - 4/BBLS OUT CEMENT @ SHOES 4BPM 300#  
88 BBLS OUT FINAL DISP PSI 800lbs - Bump Plug 1300# 90 BBLS.  
RELEASE PSI - FLOAT SHOES HELD! GOOD RETURNS THROUGH OUT JOB!

EQUIPMENT USED

NAME	UNIT NO.	NAME	UNIT NO.
<u>Chet Johnson</u>	<u>Mitch Rupp P-14</u>	<u>Scott Cassidy</u>	<u>B-3</u>
<u>James R. Thomas #44</u>			
CEMENTER OR TREATER		OWNER'S REP.	

# United Cementing and Acid Co., Inc.

**SERVICE TICKET**  
ORIGINAL 179 ✓

Oil Well Cementing & Acidizing  
(316) 321-4680 • 800-794-0187 • FAX (316) 321-4720  
2510 West 6th Street • El Dorado, KS 67042

DATE 1-10-04

COUNTY Cowley CITY \_\_\_\_\_

CHARGE TO W.D. Short

ADDRESS \_\_\_\_\_ CITY \_\_\_\_\_ ST \_\_\_\_\_ ZIP \_\_\_\_\_

LEASE & WELL NO. W. Short #1 CONTRACTOR Derentz Drilling Company

KIND OF JOB Surface SEC. 21 TWP. 33 RNG. 3E

DIR. TO LOC. Oxford 7 miles South, 3/4 East into 8:30 OLD  NEW

Quantity	MATERIAL USED	Serv. Charge	
			482.00
180 SX	class A, 3%CC, 2%gel + 1/4 Flo-seal	@ 9.90	<del>1800</del> 1800 <sup>10/10</sup>
55X	Calcium Chloride	@ 26.65	133.25
45X	gel	@ 9.70	38.80
15X	Flo-seal 450/lbs	@ 1.30	58.50
190 SX	BULK CHARGE	@ .98	186.20
58	BULK TRK. MILES 9.5 TON X .73		402.23
58	PUMP TRK. MILES	@ 2.05	118.90
—	PLUGS		99.14
		5.36 SALES TAX	<del>2392.02</del>
		TOTAL	<del>2392.02</del>

T.D. 327 ft.

SIZE HOLE 12 1/4

MAX. PRESS. \_\_\_\_\_

PLUG DEPTH CEMENT @ 297'

PLUG USED \_\_\_\_\_

REMARKS: Ran 8 5/8" to 316 ft. Brake circulation, Mix + pump 1805k class A, 3%CC 2%gel + 1/4 Flo-seal, Disp. cement to 296 ft. and shut in. Cement did circulate in cellar.

CSG. SET AT 316 ft. VOLUME 2581.57

TBG SET AT \_\_\_\_\_ VOLUME RECEIVED

SIZE PIPE 8 5/8" JUL 18 2005

PKER DEPTH \_\_\_\_\_ KCC WICHITA

TIME FINISHED 12:30

**EQUIPMENT USED**

NAME UNIT NO. NAME UNIT NO.  
Chet Johnson P-14  
James Thomas #44  
CEMENTER OR TREATER

NAME UNIT NO.  
Scott Casaday B-3  
OWNER'S REP.

**LOG-TECH, INC.**  
 1011 240th Ave.  
**HAYS, KANSAS 67601**  
 (785) 625-3858

**ORIGINAL**  
 14219

Date 3-14-2005

CHARGE TO: Short & Short, LLC.  
 ADDRESS P.O. Box 779 Oxford, Ks. 67119  
 R/A SOURCE NO. \_\_\_\_\_ CUSTOMER ORDER NO. Verbal OW  
 LEASE AND WELL NO. W.D. Short No. 1 FIELD Rainbow Bend  
 NEAREST TOWN Oxford COUNTY Cowley STATE Kansas  
 SPOT LOCATION C-1/W SEC. 21 TWP. 33S RANGE 3E  
 ZERO KB 8' AGL CASING SIZE 5.5 WEIGHT \_\_\_\_\_  
 CUSTOMER'S T.D. 3778 LOG TECH 3722 FLUID LEVEL Full  
 ENGINEER S. Chesney OPERATOR B.J. Rupp

PERFORATING							
Description	No. Shots	Depth		Amount			
		From	To				
Perforate 3 7/8 HEC	10 x 1	10	3707	3217	1650	00	
3 3/8 HEC	6 x 1+1	7	3218	3223	1500	00	
3207	3218						
7.5	7.5						
3704.5	3715.5						

DEPTH AND OPERATIONS CHARGES					
Description	Depth		Total No. Ft.	Price Per Ft.	Amount
	From	To			
Sonic Cement Handling		3722	3722	.28	1042.16
Logging Charge	3722	2500	1222	min	400.00

**RECEIVED**  
**JUL 18 2005**  
**KCC WICHITA**

MISCELLANEOUS		
Description	Quantity	Amount
Service Charge		450.00
T.J. Portable Mast		300.00
A.O.L.		
S.J.		
F.J. T.W.T.		

PRICES SUBJECT TO CORRECTION BY BILLING DEPARTMENT

RECEIVED THE ABOVE SERVICES ACCORDING TO THE TERMS AND CONDITIONS SPECIFIED ON THE REVERSE SIDE TO WHICH WE HEREBY AGREE.

.....Sub Total	<b>5342.16</b>
.....Tax	
.....	
.....	

Customer Signature \_\_\_\_\_ Date \_\_\_\_\_