

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM

WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Operator: License # 3273
Name: Herman L. Loeb
Address: P O Box 524
City/State/Zip: Lawrenceville, IL 62439
Purchaser: _____
Operator Contact Person: George A. Payne
Phone: (812) 853-3813
Contractor: Name: Val Energy, Inc.
License: 5822
Wellsite Geologist: Jon Christensen

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____

Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

1/25/2007 2/6/07 plugged
Spud Date or Date Reached TD Completion Date or Recompletion Date

API No. 15 - 007-23112-0000
County: Barber
 NW Sec. 26 Twp. 32 S. R. 14 East West
1230 feet from S / (N) (circle one) Line of Section
1160 feet from E / (W) (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Hinz Well #: 2-26
Field Name: Elsa East

Producing Formation: _____
Elevation: Ground: 1,798 ft Kelly Bushing: 1,808 ft
Total Depth: 5,081 ft Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 222 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan P+A KGR 12/12/07
(Data must be collected from the Reserve Pit)

Chloride content 36,000 ppm Fluid volume 160 bbls
Dewatering method used Hauled to SWD

Location of fluid disposal if hauled offsite: _____
Operator Name: Bemco
Lease Name: Mack SWD License No.: 32613
Quarter _____ Sec. 7 Twp. 32 S. R. 11 East West
County: Barber Docket No.: CD-78217

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: George A. Payne
Title: Petroleum Engineer Date: 4/16/07

Subscribed and sworn to before me this 18 day of April
2007

Notary Public: Rebecca J. Klopfenster
Rebecca J. Klopfenster

Commission Expires: 9/14/2014

KCC Office Use ONLY

N Letter of Confidentiality Received
If Denied, Yes Date: _____
 Wireline Log Received **RECEIVED**
 Geologist Report Received **APR 23 2007**
____ UIC Distribution **KCC WICHITA**

Drill Stem Test Summary for KCC ACO-1 Report

Operator: Herman L. Loeb
Well Name: Hinz #2-26
API #: 15-007-23112-0000

DST #1 Open 15 min, closed 45 min, open 45 min, closed 90 min

Interval tested; 4,500 to 4,553 ft
Formation: Marmaton
Initial hydrostatic: 2,109 psi
Initial flow pressure: 28 psi
Initial shut-in pressure: 535 psi
final flow pressure: 30 psi
final shut-in pressure: 437 psi
final hydrostatic: 2,105 psi
bottomhole temperature:

Fluid Recovery: 31 ft of mud with a trace of oil

DST #2 Open 15 min, closed 45 min, open 15 min, closed 45 min

Interval tested; 4,854 to 4,876 ft
Formation: Viola
Initial hydrostatic: 2,455 psi
Initial flow pressure: 28 psi
Initial shut-in pressure: 71 psi
final flow pressure: 24 psi
final shut-in pressure: 48 psi
final hydrostatic: 2,428 psi
bottomhole temperature: 122 deg F

Fluid Recovery: 31 ft of mud with a trace of oil

RECEIVED
APR 23 2007
KCC WICHITA

Allied Cementing Co., Inc
P.O. Box 31
Russell, KS 67665

4/22
250 King
1503

* I N V O I C E *

Invoice Number: 106472

Invoice Date: 02/12/07

Sold Herman Loeb Company
To: P. O. Box 524
Lawrenceville, ILL
62439

P&A

RECEIVED
APR 23 2007
KCC WICHITA


Cust I.D.....: Loeb
P.O. Number...: Henz 2-26
P.O. Date.....: 02/12/07

Due Date.: 03/14/07
Terms.....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	102.00	SKS	10.6500	1086.30	T
Pozmix	68.00	SKS	5.8000	394.40	T
Gel	9.00	SKS	16.6500	149.85	T
Handling	179.00	SKS	1.9000	340.10	T
Mileage	20.00	MILE	16.1100	322.20	T
179 sks @.09 per sk per mi					
Plug	1.00	JOB	815.0000	815.00	T
Mileage pmp trk	20.00	MILE	6.0000	120.00	T

All Prices Are Net, Payable 30 Days Following
Date of Invoice. 1 1/2% Charged Thereafter.
If Account CURRENT take Discount of 322.78
ONLY if paid within 30 days from Invoice Date

Subtotal: 3227.85
Tax.....: 203.36
Payments: 0.00
Total....: 3431.21



322.78
3,108.43

ALLIED CEMENTING CO., INC.

23497

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Mad Lodge

DATE <u>2-7-07</u>	SEC <u>26</u>	TWP <u>32s</u>	RANGE <u>14 W</u>	CALLED OUT <u>7:00AM</u>	ON LOCATION <u>9:30AM</u>	JOB START <u>11:00am</u>	JOB FINISH <u>12:45pm</u>
LEASE <u>Hemp</u>	WELL # <u>2-26</u>	LOCATION <u>160+ Lake City Rd</u>	COUNTY <u>Barber</u>	STATE <u>KS</u>			
OLD OR NEW (Circle one) <u>NEW</u>			<u>365</u>	<u>Winto</u>			

CONTRACTOR Val # 3

TYPE OF JOB Qty Plug

HOLE SIZE 7 7/8 T.D. 750ft

CASING SIZE _____ DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 300 MINIMUM 100

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT 7 bbls

OWNER Herman Zael

CEMENT AMOUNT ORDERED 170 x 60/40

62 gel

COMMON	<u>102 A</u>	@	<u>10.65</u>	<u>1086.30</u>
POZMIX	<u>68</u>	@	<u>5.80</u>	<u>394.40</u>
GEL	<u>9</u>	@	<u>16.65</u>	<u>149.85</u>
CHLORIDE		@		
ASC		@		

RECEIVED
APR 23 2007
KCC WICHITA

EQUIPMENT

PUMP TRUCK # 372 CEMENTER Mary HELPER Darin

BULK TRUCK # 389 DRIVER AR

BULK TRUCK # _____ DRIVER _____

HANDLING	<u>179</u>	@	<u>1.90</u>	<u>340.10</u>
MILEAGE	<u>20 x 179 x .09</u>			<u>322.20</u>
				TOTAL <u>2292.85</u>

REMARKS:

1st plug 50% at 750ft pump 20 bbls with mix 50% + displace 7 bbls
2nd plug 75% at 240ft pump 20 bbls water mix 75% + displace 2 bbls
3rd plug 90% at 60ft mouse hole 10% Rot hole 15%

SERVICE

DEPTH OF JOB	<u>750ft</u>			
PUMP TRUCK CHARGE				<u>815.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>20</u>	@	<u>6.00</u>	<u>120.00</u>
MANIFOLD		@		
		@		
		@		

TOTAL 935.00

CHARGE TO: Herman Zael

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

	@		
	@		
	@		
ANY APPLICABLE TAX	@		
WILL BE CHARGED UPON INVOICING			
		TOTAL	

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE [scribble]

DISCOUNT [scribble] IF PAID IN 30 DAYS

SIGNATURE [Signature]

[Signature]
PRINTED NAME

Allied Cementing Co., Inc
P.O. Box 31

Russell, KS 67665

* * * * *
* I N V O I C E *
* * * * *

Invoice Number: 106317

Invoice Date: 01/31/07

4122
250 Hinz
1567

Sold Herman Loeb Company
To: P. O. Box 524
Lawrenceville, ILL
62439

Surface casing

Cust I.D.....: Loeb
P.O. Number...: Hinz 2-26
P.O. Date.....: 01/31/07

Due Date.: 03/02/07
Terms....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	250.00	SKS	10.6500	2662.50	T
Gel	5.00	SKS	16.6500	83.25	T
Chloride	9.00	SKS	46.6000	419.40	T
Handling	264.00	SKS	1.9000	501.60	E
Mileage	20.00	MILE	23.7600	475.20	E
264 sks @ >09 per sk per mi					
Surface	1.00	JOB	815.0000	815.00	E
Mileage pmp trk	20.00	MILE	6.0000	120.00	E
Head Rental	1.00	PER	100.0000	100.00	E

All Prices Are Net. Payable 30 Days Following
Date of Invoice. 1 1/2% Charged Thereafter.
If Account CURRENT take Discount of 517.69
ONLY if paid within 30 days from Invoice Date

Subtotal: 5176.95
Tax.....: 199.40
Payments: 0.00
Total....: 5376.35

Discount - 517.69

SKS	250.00	10.6500	2662.50	T
SKS	5.00	16.6500	83.25	T
SKS	9.00	46.6000	419.40	T
SKS	264.00	1.9000	501.60	E
MILE	20.00	23.7600	475.20	E
JOB	1.00	815.0000	815.00	E
MILE	20.00	6.0000	120.00	E
PER	1.00	100.0000	100.00	E

4,858.66
Pd. 2-19-07
#72827

RECEIVED
APR 23 2007
KCC WICHITA

ALLIED CEMENTING CO., INC.

26163

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Medicine Lodge
1-26-07 1-26-07

DATE <i>01-25-07</i>	SEC <i>26</i>	TWP <i>32s</i>	RANGE <i>14W</i>	CALLED OUT <i>4:30 PM</i>	ON LOCATION <i>6:30 PM</i>	JOB START <i>1:30 AM</i>	JOB FINISH <i>2:00 AM</i>
LEASE <i>Honz</i>	WELL # <i>2+26</i>	LOCATION <i>160+ LAKE CITY ROAD</i>			COUNTY <i>BARBER</i>	STATE <i>KANSAS</i>	
OLD OR NEW (Circle one) <u>NEW</u>			<i>3 3/4 SOUTH, WEST INTO</i>				

CONTRACTOR *VAL #3*

TYPE OF JOB *SURFACE CASING*

HOLE SIZE *17 1/2"* T.D. *222'*

CASING SIZE *13 3/8"* DEPTH *222'*

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX *100#* MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. *15'*

PERFS. _____

DISPLACEMENT *31 BBLs. WATER*

OWNER *HERMAN C. COEB*

CEMENT AMOUNT ORDERED *250x CLASS A +3%CC +2%GEL*

COMMON <i>A 250</i>	@	<i>10.65</i>	<i>2662.50</i>
POZMIX _____	@		
GEL <i>59</i>	@	<i>16.65</i>	<i>83.25</i>
CHLORIDE <i>9</i>	@	<i>46.60</i>	<i>419.40</i>
ASC _____	@		
HANDLING <i>264</i>	@	<i>1.90</i>	<i>501.60</i>
MILEAGE <i>264 x 20</i>	@	<i>.09</i>	<i>475.20</i>
TOTAL			<i>4141.95</i>

EQUIPMENT

PUMP TRUCK CEMENTER *R. BRUNOARDI*

444-302 HELPER *D. CUSHENBERY*

BULK TRUCK # *356-244* DRIVER *R. McKENNEY*

BULK TRUCK # _____ DRIVER _____

REMARKS:

RUN 13 3/8" CS6 + BREAK CIRC.

PUMP 5 BBLs. FRESH WATER

MIX 250x CLASS A +3%CC +2%GEL

DISPLACE CEMENT / 31 BBLs

CEMENT DID CIRCULATE

SERVICE

DEPTH OF JOB <i>222'</i>		
PUMP TRUCK CHARGE		<i>815.00</i>
EXTRA FOOTAGE	@	
MILEAGE <i>20</i>	@	<i>6.00 120.00</i>
MANIFOLD	@	
<i>HEAD RENTAL</i>	@	<i>100.00 100.00</i>
TOTAL <i>1035.00</i>		

CHARGE TO: *HERMAN C. COEB*

STREET *P.O. Box 524*

CITY *LAURENCEVILLE* STATE *ILL.* ZIP *62439*

RECEIVED
APR 23 2007

KCC WICHITA

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

SIGNATURE *X Ren Moon*

TAX _____

TOTAL CHARGE ~~_____~~

DISCOUNT ~~_____~~ IF PAID IN 30 DAYS

PRINTED NAME _____