

15-065-21091-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 23 Twp. 9S Rge. 23W ~~E/W~~
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE/4 NE/4 SW/4

Lease Owner Frontier Oil Company
Lease Name Riffel Well No. 1
Office Address 1720 KSB&T Building, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

D & A
Date Well completed January 24, 1979
Application for plugging filed January 24, 1979
Application for plugging approved January 24, 1979
Plugging commenced January 24, 1979
Plugging completed January 24, 1979
Reason for abandonment of well or producing formation
D & A

If a producing well is abandoned, date of last production 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3960'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	253.30'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 900' w/70 sx cement
Plug @ 240' w/20 sx cement
Bridge plug @ 40' w/10 sx cement
5 sx cement in rathole

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1979

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company & Allied Cementing 2-15-79
1720 KSB&T Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Gloria Fawcett (employee of owner) ~~xxxxxxxxxx~~


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett
1720 KSB&T Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of January, 1979.

Joyce A. Hagermann
Notary Public.

My commission expires _____



15-065-21091-00-00

DRILLERS LOG

No. 1 Riffel

CASING RECORD:	COMPANY:	Frontier Oil Company	DESCRIPTION:
8 5/8" @ 260' w/170 sx cement	CONTRACTOR:	Red Tiger Drilling Company	NE/4 NE/4 SW/4 Sec. 23-T9S-R23W Graham County, Kansas
	COMMENCED:	December 31, 1978	
	COMPLETED:	January 24, 1978 ⁹	
TOTAL DEPTH: 3,960'			ELEVATION: 2,386' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Sand	0	260	
Shale	260	400	
Sand & Shale	400	1610	
Shale	1610	1729	
Hard Sand	1729	1780	
Hard Sand & Shale	1780	1991	
Anhydrite	1991	2025	
Shale	2025	2388	
Shale & Lime Streaks	2388	2513	
Shale & Lime	2513	2626	
Lime & Shale	2626	2806	
Shale & Lime Streaks	2806	2876	
Shale & Lime	2876	3007	
Lime & Shale	3007	3360	
Shale	3360	3455	
Lime	3455	3960	
RTD		3960	


I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 31st day of January, 1979.

Joyce A. Hagermann
Notary Public



RECEIVED
STATE CORPORATION COMMISSION
2-15-79
FEB 15 1979
CONSERVATION DIVISION
Wichita, Kansas