

RECEIVED
 JAN 26 1989
 01-26-1989
 CONSERVATION DIVISION
 Wichita, Kansas

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Price

WELL NUMBER 1-19

330 Ft. from S Section Line

390 Ft. from E Section Line

SEC. 19 TWP. 10S RGE. 32 ~~XXXX~~(W)

COUNTY Thomas

Date Well Completed 1-12-89

Plugging Commenced 1-12-89

Plugging Completed 1-13-89

LEASE OPERATOR Brito Oil Company, Inc.

ADDRESS 200 E. First, Suite 413, Wichita, KS 67202

PHONE#(316) 263-8787 OPERATORS LICENSE NO. 4629

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-12-89 (date)

by State Pluggger, Bruce Basye (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	322'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Circulate heavy mud in hole. 1st plug from 2650' to 2550' w/25 sx. 2nd plug from 1800' to 1400' w/100 sx and 1 sack Flocel. 3rd plug from 372' to 212' w/40 sx. 4th plug from 40' to surface with wiper plug w/15 sx. Rathole-15 sx. All cement 60/40 posmix, 6% gel, 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brito Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801
 Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 24th day of January, 19 89

Janet A. Stuck
 Notary Public

My Commission Expires: 12-29-90

