

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20,583-00-00

LEASE NAME Soucie

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1 2-19

2310' Ft. from N Section Line

990' Ft. from W Section Line

LEASE OPERATOR Brito Oil Co., Inc.

SEC. 19 TWP. 10 RGE. 32 ~~X~~ W

ADDRESS 200 E. First - Suite 208
Wichita, KS 67202

COUNTY Thomas

PHONE#(316) 263-8787 OPERATORS LICENSE NO. 4629

Date Well Completed 12-11-91

Character of Well D & A

Plugging Commenced 12-11-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-11-91

The plugging proposal was approved on December 11, 1991 (date)

by Marvin Miller (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom T.D. 4700'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	260'	None

DEC 20 1991
12-20-1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Spotted 35 sx. cement at 2615' thru drill pipe. Spotted 15 sx. cement in
Spotted 100 sx. cement at 1805' thru drill pipe. rathole.
Spotted 40 sx. cement at 310' thru drill pipe.
Spotted 10 sx. cement w/ wiper plug at 40' thru drill pipe.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address P. O. Box 48848, Wichita, KS 67201-8848

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brito Oil Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael L. Considine


(Address) P. O. Box 48848
Wichita, KS 67201-8848

SUBSCRIBED AND SWORN TO before me this 17th day of December, 19 91

My Commission Expires:



Notary Public


 RECEIVED
 STATE COMMISSION

 DEC 20 1991
 12-20-1991
 STATE COMMISSION

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Brito Oil Co., Inc., 200 E. First - Suite 208,
 Wichita, KS 67202
 CONTRACTOR: White & Ellis Drilling, Inc. 401 E. Douglas - Suite 500
 Wichita, Kansas 67202

Lease Name Soucié Well No. 2-19
 Sec. 19 T. 10S R. 32W Spot SE SW NW
 County Thomas State Kansas Elev. _____

Casing Record:

Surface: 8 5/8" @ 260' with 160 sx.

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4700'

Drilling Commenced 12-1-91 Drilling Completed 12-11-91

Formation	From	To	Tops	
Cellar	0	5	Anhydrite	2601
Shale & Shells	5	970	Kansas City	4110
Shale & Lime	970	1639		
Shells & Shale	1639	1830		
Shells, Shale & Lime	1830	2194		
Lime & Shells	2194	2256		
Shale & Sand Streaks	2256	2630		
Shale	2630	2645		
Shale & Lime	2645	4045		
Lime & Shale	4045	4265		
Lime	4265	4700		