

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: AX&P, Inc.
Address: P.O. Box 1176 Ind. KS 67301
Phone: (620) 325-5212 Operator License #: 3830
Type of Well: oil well Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: October 6, 2006 (Date)
by: T. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Neodesha Sd Depth to Top: 800 Bottom: 815 T.D. 837'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-205-19631-00-00
Lease Name: Unit 1 - Ellis
Well Number: Ellis #4
Spot Location (QQQQ): NW SE SE SE
400 Feet from North / South Section Line
400 Feet from East / West Section Line
Sec. 29 Twp. 30 S. R. 16 East West
County: Wilson
Date Well Completed: 2/20/1954
Plugging Commenced: 11/1/06
Plugging Completed: 11/6/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Neodesha Sd.</u>	<u>Oil</u>	<u>0</u>	<u>30</u>	<u>8 5/8</u>	<u>30</u>	<u>0</u>
		<u>0</u>	<u>782'</u>	<u>2"</u>	<u>732'</u>	<u>450'</u>
		<u>0</u>	<u>650'</u>	<u>4 7/8"</u>	<u>751'</u>	<u>0</u>

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 20 2008

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

POH 1" pumping string and pump. Tried to POH 2"; parted @100' down.
Fished for 2" ; POH 21 joints (450') 2"; Fished for 2", but could not fish 2". Got permission to plug. Perforated 250', 125', 75'.
RIH 1" and spotted bottom plug. Pulled up to 250' and cemented to surface. Topped off after POH 1" pipe. 110 sx total

Name of Plugging Contractor: AX&P, Inc. (Rick's well service) License #: 3830
Address: _____

Name of Party Responsible for Plugging Fees: AX&P, Inc. P.O. Box 1176 Independence, KS 67301

State of Missouri County, Jackson, ss.

J J Hanke (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 2042 2nd Rd Neodesha, ks 66757

JOHN T. JAMES
Notary Public-Notary Seal
STATE OF MISSOURI
Jackson County
My Commission Expires April 24, 2011
Commission # 07040939

and SWORN TO before me this 11 day of October, 20 08
Notary Public My Commission Expires: April 24, 2011

Rick's Well Service

P.O. Box 268
 129 Railroad
 Cherryvale, KS 67335

rickswellservice@sbcglobal.net

Invoice

DATE	INVOICE #
12/18/200	2604

BILL TO
AX&P Inc. Rt. 2 Box 225 Neodesha, KS 66757

Ellis OW#4

DATE	DESCRIPTION	UNITS	RATE	AMOUNT
10/31/200	Pulled 31 Jts. 1" pipe and pump. Pulling Unit	2	90.00	180.00T
11/2/2006	Pulled 21 jts. 2" pipe. Pulling Unit	2	90.00	180.00T
11/3/2006	Ran in 20 jts. 2" pipe, tried to fish, pulled pipe out, went to C'vale shop for fishing tool, ran in tool and fish for pipe, could not fish, pull tool out. Pulling Unit	5.5	90.00	495.00T
11/6/2006	Ran in 1" pipe to plug, dig circ pit w/dozer, circ. gel and spot bottom plug, pull pipe up to 250', circ. cement to surf., pull pipe out, top off w/cement, fill circ. pit w/dozer. Pulling Unit	4.5	90.00	405.00T
	Pump charge		500.00	500.00T
	110 sacks cement	110	8.10	891.00T
	6 sacks of bentonite	6	10.00	60.00T
	dozer	2	75.00	150.00T
	Sales Tax		7.00%	200.27

RECEIVED
 KANSAS CORPORATION COMMISSION
 OCT 20 2008
 CONSERVATION DIVISION
 WICHITA, KS

MAKE CHECKS PAYABLE TO:
 Rick's Well Service
 THANK YOU!

Total	\$3,061.27
--------------	-------------------

