

15-179-20284-00-00

SP

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sheridan County, Sec. 28 Twp. 10 Rge. 27 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C SW NE  
Lease Owner Dreiling Oil, Inc.  
Lease Name Gugler Well No. 1  
Office Address Route # 2 Victoria, Kansas 67671  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-27 19 71  
Application for plugging filed 5-27 19 71  
Application for plugging approved 5-27 19 71  
Plugging commenced 5-27 19 71  
Plugging completed 5-27 19 71  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey Hays, Kansas 67601  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8	208'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug was set at 1225' with 100 cu. ft. cement  
2nd plug was set at 215' with 25 cu. ft. cement  
3rd plug was set at 40' with 10 cu. ft. cement

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 7 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
06-07-1971

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dreiling Oil, Inc.  
Address Victoria, Kansas 67671


STATE OF ~~KANSAS~~ Kansas, COUNTY OF Ellis, ss.  
I, Leo F. Dreiling, Pres. of Drilg. Contr. of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling  
Leo F. Dreiling, Route # 2, Victoria, Kansas 67671  
(Address)

Subscribed and sworn to before me this 2nd day of June, 19 71

My commission expires January 13, 1975

Patty Dreiling  
PATTY DREILING Notary Public.



# DREILING OIL, INC.

Victoria, Kansas 67671

15-179-20284-00-00  
WELL LOG

Company **Dreiling Oil, Inc.**  
**Route # 2**  
**Victoria, Kansas 67671**

Farm **Gugler** No. **1**

Total Depth **4115'**

Comm. **5-22-71** Comp. **5-27-71**

Contractor **Dreiling Oil, Inc.**  
**Victoria, Kansas 67671**

Sec. 28 Twp. 10 Rng. 27

Location **C SW NE**

County **Sheridan**

Elevation: **2670'** **K. B.**

**2667'** **D. F.**

**2665'** **G. R.**

Casing Record  
**208' - 8 5/8**

Cement Record  
**160 sacks cement**

Production:  
**D & A**

Figures Indicate Bottom of Formations

0'	40'	Surface Soil Clay
60'	140'	Yellow Clay
140'	208'	Blue Shale
208'	1090'	Shale
1090'	1340'	Sand
1340'	1470'	Shale & Sand Streaks
1470'	1871'	Shale & Sand Streaks
1871'	2020'	Sand
2020'	2238'	Red Bed
2238'	2260'	Anhydrite
2260'	2276'	Anhydrite
2276'	2570'	Shale
2570'	2915'	Shale & Lime
2915'	3195'	Lime & Shale
3195'	3380'	Lime & Shale
3380'	3535'	Lime & Shale
3535'	3765'	Lime & Shale
3765'	3885'	Lime
3885'	3985'	Lime
3985'	4040'	Lime
4040'	4056'	Lime
4056'	4115'	Lime
4115'	T. D.	

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 7 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
06-07-1971

STATE OF KANSAS)  
                  )ss  
COUNTY OF ELLIS)

I, Leo F. Dreiling, of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Gugler # 1.

LEO F. DREILING

Subscribed and sworn to before me this 2nd day of June, 1971.



PATTY DREILING NOTARY PUBLIC

My Commission expires: January 13, 1975