

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Mull Drilling Company, Inc. Address: P.O. Box 2758, Wichita KS, 67201-2758 Phone: (316) 264-6366 Operator License #: 5144 Type of Well: D&A Docket #: N/A The plugging proposal was approved on: 9/29/08 by: Jack Maclaskey Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet)

API Number: 15 - 135-24840-00-00 Lease Name: Toedman "A" Well Number: #1-16 Spot Location (QQQQ): NE - SW - NW - NE 699 Feet from North / South Section Line 2304 Feet from East / West Section Line Sec. 16 Twp. 16 S. R. 22 East West County: Ness Date Well Completed: 10/2/08 Plugging Commenced: 10/3/08 Plugging Completed: 10/3/08

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: 0', 219', 8 5/8", 211.93', 0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st plug: 1760' w/50 sacks; 2nd plug: 1180' w/80 sacks; 3rd plug: 600' w/50 sacks; 4th plug @ 240' w/40 sacks and 20 sacks @ 60' 15 sacks in rathole, 255 sacks 60/40 Poz, 4% gel, 1/4# floseal per sack.

RECEIVED KANSAS CORPORATION COMMISSION

OCT 29 2008

Name of Plugging Contractor: WW Drilling, LLC License #: 33575 Address: P.O. Box 307, WaKeeney KS 67672

CONSERVATION DIVISION WICHITA, KS


Name of Party Responsible for Plugging Fees: Mull Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Mark A. Shreve, President/COO (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) P.O. Box 2758 Wichita KS 67201-2758



SUBSCRIBED and SWORN TO before me this 28th day of October, 2008

Tannis L. Tritt My Commission Expires: 3-26-2011 Notary Public

Handwritten initials 'PT'

**WW Drilling, LLC**  
**WaKeeney, KS**  
**Well Plugging Orders**

Operator: Mull Drilling Company License # 5144  
Address: 221 N Main STE 300, PO Box 2758, Wichita KS, 67202

API # 15-135-24840-00-00

Lease Name: Toedman A #1-16  
Legals: 699 FNL & 2304 FEL, Section 16-16s-22w  
County: Ness  
State: KS

Plug #	Sx.		Feet
1st	<u>50</u>	@	<u>1760</u>
2nd	<u>80</u>	@	<u>1180</u>
3rd	<u>50</u>	@	<u>600</u>
4th	<u>40</u>	@	<u>240</u>
5th	<u>20</u>	@	<u>60</u>
Rathole	<u>15</u>		
Mousehole	<u>        </u>		

Total: 255

Type: 60/40 Poz - 4% Gel - 1/4 # per sx flo-seal

Spud Report: Steve Durrant Date: 9/26/2008 Time: 9:45 AM

Orders From: Jack Maclasky Date: 9/29/2008 Time: 8:30 AM

Reported to: Michael Maier Date: 10/6/2008 Time: 2:00 PM

Results: D & A

# ALLIED CEMENTING CO., LLC. 32950

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Ness City

DATE <u>10-3-08</u>	SEC. <u>16</u>	TWP. <u>76S</u>	RANGE <u>22W</u>	CALLED OUT <u>12:00 AM</u>	ON LOCATION <u>4:30 AM</u>	JOB START <u>8:30 AM</u>	JOB FINISH <u>9:00 AM</u>
LEASE <u>Toedman A</u>		WELL# <u>1-16</u>		LOCATION <u>4 + 147 St, 2N, 13W</u>		COUNTY <u>Ness</u>	STATE <u>Ks</u>
OLD OR <input checked="" type="radio"/> NEW (Circle one)			<u>5/3</u>				

CONTRACTOR W-W #2

TYPE OF JOB Rotary plug

HOLE SIZE 7 7/8" I.D. 4498'

CASING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE 4 1/2" DEPTH 1760'

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX 200# MINIMUM 0

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT Freshwater + mud

OWNER Mull Drilling

CEMENT AMOUNT ORDERED 255 sx 60/40 4% Gel 1/2# Flg - seal

COMMON	<u>153 sx</u>	@ <u>13.65</u>	<u>2,088.45</u>
POZMIX	<u>102 sx</u>	@ <u>7.60</u>	<u>775.20</u>
GEL	<u>102 sx</u>	@ <u>20.40</u>	<u>204.00</u>
CHLORIDE		@	
ASC		@	
<u>Flg - seal</u>	<u>55#</u>	@ <u>2.45</u>	<u>134.75</u>
		@	
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>267 sx</u>	@ <u>2.25</u>	<u>1060.75</u>
MILEAGE	<u>267 X 24 X .10</u>		<u>1640.80</u>
TOTAL			<u>4,443.95</u>

**EQUIPMENT**

PUMP TRUCK # 947 CEMENTER Rick H.  
HELPER Alvin R.

BULK TRUCK # 456-241 DRIVER Chris H. / Kevin W.

BULK TRUCK # \_\_\_\_\_ DRIVER \_\_\_\_\_

**REMARKS:**

- 50 sx - 1760'
- 80 sx - 1180'
- 50 sx - 600'
- 40 sx - 240'
- 20 sx - 60'
- Rathole - 15 sx
- 255 sx 60/40 4% Gel 1/2# Flg - seal

**SERVICE**

DEPTH OF JOB 1760'

PUMP TRUCK CHARGE \_\_\_\_\_ 1000.00

EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_

MILEAGE 24 @ 7.50 180.00

MANIFOLD \_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL 1180.00

CHARGE TO: Mull Drilling

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**PLUG & FLOAT EQUIPMENT**

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL \_\_\_\_\_

To Allied Cementing Co., LLC.  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME N. Lonnie Lang

SIGNATURE N. Lonnie Lang

SALES TAX (If Any) \_\_\_\_\_

TOTAL CHARGES \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS