

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: James B. Ash d/b/a Jaguar Oil & Gas  
Address: 201 Susan Lane, Andover, Kansas 67002  
Phone: (316) 733-8684 Operator License #: 33398  
Type of Well: D & A Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 08-29-08 (Date)  
by: Jeff Glock (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-173-20997-0000  
Lease Name: George/GWA  
Well Number: 1  
Spot Location (QQQQ): C - NW - SE - NE  
1650 Feet from  North /  South Section Line  
990 Feet from  East /  West Section Line  
Sec. 35 Twp. 25 S. R. 1  East  West  
County: Sedgwick  
Date Well Completed: 08-29-08 RECEIVED  
Plugging Commenced: 08-29-08 KANSAS CORPORATION COMMISSION  
Plugging Completed: 09-04-08 OCT 29 2008  
CONSERVATION DIVISION  
WICHITA, KS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	GL	216	8 5/8	212	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

On 8-29-08, ran 4 1/2" drill pipe to 2180'. Mix & pump 35 sx 60/40 poz 4% gel & displace. On 9-04-08 ran 2 7/8" tubular goods to 265'. Mix & pump 35 sx 60/40 poz 4% gel & displace. Pulled 2 7/8" tubular goods up to 64'. Mix & pump 25 sx 60/40 poz 4% gel to surface. Cement circulated in the cellar. Verified cement level stayed up. Mix & pump 15 sx in the rathole.


Name of Plugging Contractor: AA Drilling and Had-A-Call Well Service License #: (AA-#32753) (Had-A-Call - #31538)  
Address: P.O. Box 771189, Wichita, KS 67277 15951 E. 101st N., Benton, KS 67017

Name of Party Responsible for Plugging Fees: James B. Ash d/b/a Jaguar Oil & Gas

State of Kansas County, Butler, ss.

James B. Ash (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) James B. Ash  
(Address) 201 Susan Lane, Andover, KS 67002



SUBSCRIBED and SWORN TO before me this 28<sup>th</sup> day of OCTOBER, 2008  
\_\_\_\_\_  
Notary Public My Commission Expires: 11/9/2011

# WELL LOG

James B. Ash d/b/a Jaguar Oil & Gas  
#1 GEORGE/GWA  
C NW SE NE  
Section 35-T25S-R1E

Elevation 1389 KB

Formation (Top), Depth and Datum		(Sample)
Name	Top	Datum
Brown Lime	2191	(-802)
Kansas City	2532	(-1143)
Base Kansas City	2704	(-1315)
Mississippian	3004	(-1615)
Hunton	3416	(-2027)
Total Depth	3422	(-2033)

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 29 2008

CONSERVATION DIVISION  
WICHITA, KS