

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc
Address: PO Box 2528 Liberal KS 67905
Phone: 620 629 4200 Operator License #: 5447
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9-15-08 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Morrow Depth to Top: 5518 Bottom: 5122 T.D. 6625
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-129-21015-00-00
Lease Name: Dunigan A
Well Number: 2
Spot Location (QQQQ): SW-SE-NE
2310 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 4 Twp. 32 S. R. 39 East West
County: Morton
Date Well Completed: 9-3-89 spud
Plugging Commenced: 9-16-08
Plugging Completed: 9-19-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				20	48	-
				8 5/8	1723	-
				5 1/2	6024	350

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 200 lb. hulls + 25 sx cmt. to plug perfs from 5518 to 5318
5 1/2 showed stuck below 350. Ran 2 3/8 to 1750. Mixed 35 sx
plug in 5 1/2 from 1750 to 1470. Shot 5 1/2, circ. hole w/mud mixed 55 sx
350 to 185 10sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49, BA, Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Oxy USA Inc 1701 N. Kansas PO Box 2528 Liberal, KS. 67905
State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) PO Box 2528 Liberal, KS. 67905

ANITA PETERSON
Notary Public - State of Kansas
My Appt. Expires October 19, 2008

My Commission Expires: Oct. 1, 2009
Subscribed and sworn to before me this 27 day of Oct. 2008
Anita Peterson
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 03 2008

CONSERVATION DIVISION
WICHITA, KS